

Application

Name:

04774 0040 Deadway Madamiration					
04774 - 2016 Roadway Modernization					
05014 - CSAH 66 (Golden Valley Road) Reconstruction					
Regional Solicitation - Roadways Including Multimodal E	Elements				
Status:	Submitted				
Submitted Date:	07/15/2016 10:39 AM				
Primary Contact					
Name:*		Carla	J	Stueve	
Name.	Salutation	First Name	Middle Name	Last Name	
Title:	Transportation	on Engineer			
Department:					
Email:	Carla.Stueve@hennepin.us				
Address:	1600 Prairie Drive				
*	Medina	Minne	esota	55340	
	City	State/Pro	ovince	Postal Code/Zip	
Phone:*	612-596-0356				
Thomas	Phone		Ext.		
Fax:					
What Grant Programs are you most interested in?	Regional Solicitation - Roadways Including Multimodal Elements				
Organization Information					

HENNEPIN COUNTY

Jurisdictional Agency (if different):			
Organization Type:	County Government		
Organization Website:			
Address:	DPT OF PUBLIC WORKS		
	1600 PRAIRIE DR		
*	MEDINA	Minnesota	55340
	City	State/Province	Postal Code/Zip
County:	Hennepin		
Phone:*	763-745-7600		
Thore.		Ext.	
Fax:			
PeopleSoft Vendor Number	0000028004A9		

# **Project Information**

Project Name

CSAH 66 (Golden Valley Road) Reconstruction /

Modernization

Hennepin

Primary County where the Project is Located

Jurisdictional Agency (If Different than the Applicant):

The CSAH 66 (Golden Valley Road) project reconstructs a 0.93 mile section of roadway from Regent Avenue to Bonnie Lane in the City of Golden Valley. The project objectives are to provide a safe, comfortable, and inviting corridor for people living, working, or visiting the area by improving safety and operations for pedestrian, bicycle, transit, vehicle, and freight travel movements along the corridor. West of Noble Avenue, CSAH 66 will have a three-lane typical section with two travel lanes and a center turn lane. East of Noble Avenue, CSAH 66 will include two travel lanes with dedicated turn lanes provided at signalized intersections. A planted boulevard, sidewalk, and trail will be included throughout the project corridor. Intersection geometry and signal upgrades will improve the safety and level of service for all modes.

Brief Project Description (Limit 2,800 characters; approximately 400 words)

The project will incorporate the following improvements, pending final approval by the Golden Valley City Council:

- 1.Replace sidewalks, fill sidewalk gaps, and relocate obstructing utilities
- 2.Construct the Bassett Creek Regional Trail along project's full extent
- 3.Upgrade pedestrian and bicycle crossings with ADA compliant ramps, Accessible Pedestrian Signals (APS), durable crosswalk markings, pedestrian median islands, and countdown timers
- 4.Add planted boulevards to increase green space and buffer sidewalk and trail users from traffic
- 5.Enhance streetscaping with lighting and other elements

6.Improve efficiency and safety by converting an unwarranted all-way stop at CSAH 66/Regent Avenue to a two-way stop with a center median, providing flashing yellow arrows at signalized intersections, and reconfiguring striping and turn lanes

When complete, this project will achieve a safe and inviting corridor for all ages, physical abilities, and travel modes. Improvements will provide additional multimodal travel benefits when the Blue Line Extension becomes operational, as the CSAH 66 corridor provides a direct connection to the proposed future Golden Valley Bottineau Blue Line LRT station at CSAH 66 and Theodore Wirth Parkway.

Include location, road name/functional class, type of improvement, etc.

<u>TIP Description Guidance</u> (will be used in TIP if the project is selected for funding)

selected for fullding)

**Project Length (Miles)** 

CSAH 66 (GOLDEN VALLEY RD) FROM REGENT AVE TO BONNIE LANE IN GOLDEN VALLEY - RECONSTRUCT ROADWAY, CURB AND GUTTER, SIDEWALK, TRAIL FOR PEDS AND BIKES, TRAFFIC SIGNALS, AND STREETSCAPING.

0.93

## **Project Funding**

Are you applying for funds from another source(s) to implement this project?

No

If yes, please identify the source(s)

Federal Amount \$7,000,000.00

Match Amount \$1,761,000.00

Minimum of 20% of project total

**Project Total** \$8,761,000.00

Match Percentage 20.1%

Minimum of 20%

Compute the match percentage by dividing the match amount by the project total

Source of Match Funds Local

A minimum of 20% of the total project cost must come from non-federal sources; additional match funds over the 20% minimum can come from other federal sources

#### **Preferred Program Year**

Select one: 2020

For TDM projects, select 2018 or 2019. For Roadway, Transit, or Trail/Pedestrian projects, select 2020 or 2021.

#### **Additional Program Years:**

Select all years that are feasible if funding in an earlier year becomes available.

## **Specific Roadway Elements**

CONSTRUCTION PROJECT ELEMENTS/COST ESTIMATES	Cost
Mobilization (approx. 5% of total cost)	\$450,000.00
Removals (approx. 5% of total cost)	\$450,000.00
Roadway (grading, borrow, etc.)	\$836,000.00
Roadway (aggregates and paving)	\$1,364,000.00
Subgrade Correction (muck)	\$0.00
Storm Sewer	\$700,000.00
Ponds	\$80,000.00
Concrete Items (curb & gutter, sidewalks, median barriers)	\$325,000.00
Traffic Control	\$75,000.00
Striping	\$65,000.00
Signing	\$15,000.00
Lighting	\$0.00
Turf - Erosion & Landscaping	\$250,000.00
Bridge	\$0.00
Retaining Walls	\$1,000,000.00
Noise Wall (do not include in cost effectiveness measure)	\$0.00
Traffic Signals	\$500,000.00
Wetland Mitigation	\$0.00
Other Natural and Cultural Resource Protection	\$0.00
RR Crossing	\$0.00
Roadway Contingencies	\$1,170,000.00
Other Roadway Elements	\$500,000.00
Totals	\$7,780,000.00

## **Specific Bicycle and Pedestrian Elements**

CONSTRUCTION PROJECT ELEMENTS/COST ESTIMATES	Cost
Path/Trail Construction	\$350,000.00
Sidewalk Construction	\$150,000.00
On-Street Bicycle Facility Construction	\$0.00
Right-of-Way	\$0.00
Pedestrian Curb Ramps (ADA)	\$150,000.00
Crossing Aids (e.g., Audible Pedestrian Signals, HAWK)	\$50,000.00
Pedestrian-scale Lighting	\$100,000.00
Streetscaping	\$75,000.00
Wayfinding	\$6,000.00
Bicycle and Pedestrian Contingencies	\$50,000.00
Other Bicycle and Pedestrian Elements	\$50,000.00
Totals	\$981,000.00

# **Specific Transit and TDM Elements**

CONSTRUCTION PROJECT ELEMENTS/COST ESTIMATES	Cost
Fixed Guideway Elements	\$0.00
Stations, Stops, and Terminals	\$0.00
Support Facilities	\$0.00
Transit Systems (e.g. communications, signals, controls, fare collection, etc.)	\$0.00
Vehicles	\$0.00
Contingencies	\$0.00
Right-of-Way	\$0.00
Other Transit and TDM Elements	\$0.00
Totals	\$0.00

# **Transit Operating Costs**

Number of Platform hours	0
Cost Per Platform hour (full loaded Cost)	\$0.00
Substotal	\$0.00
Other Costs - Administration, Overhead,etc.	\$0.00

#### **Totals**

Total Cost \$8,761,000.00

Construction Cost Total \$8,761,000.00

Transit Operating Cost Total \$0.00

## **Requirements - All Projects**

### **All Projects**

1. The project must be consistent with the goals and policies in these adopted regional plans: Thrive MSP 2040 (2014), the 2040 Transportation Policy Plan, the 2040 Regional Parks Policy Plan (2015), and the 2040 Water Resources Policy Plan (2015).

#### Check the box to indicate that the project meets this requirement. Yes

2. The project must be consistent with the 2040 Transportation Policy Plan. Reference the 2040 Transportation Plan objectives and strategies that relate to the project.

- A) Transportation System Stewardship: The CSAH 66 project provides a new and structurally adequate roadway that accommodates forecasted 2040 traffic volumes. This A-Minor Arterial functions as an Augmentor and provides an essential east-west connection between North Minneapolis and Golden Valley. This project is a preferred alignment for the Hennepin County Bicycle Transportation Plan, Metropolitan Council Regional Bicycle Transportation Network, and the Three Rivers Park District's Bassett Creek Regional Trail.
- B) Safety/Security: Planted boulevards and curb enhancements will provide delineation between modes. ADA compliant ramps, pedestrian median islands, countdown timers and crosswalk markings will significantly enhance safety for all users along the corridor. Driver safety and efficiency will also be improved through removal of an unwarranted all-way stop.

List the goals, objectives, strategies, and associated pages:

- C) Access to Destinations: CSAH 66 is a regionally significant corridor that provides a direct connection to TH 100 and serves as a key alternate to TH 55 during periods of construction or congestion. This project will connect all modes and users directly to the Bottineau LRT Station and park & ride at Golden Valley Road. Metro Transit local bus route 14 and express route 758 provide connections to Minneapolis, Robbinsdale, and other cities. Theodore Wirth Park and the Grand Rounds Regional Trail are immediately east of the roadway and attract visitors year round from the local area and broader region.
- D) Competitive Economy: Courage Kenny Rehabilitation and other vital medical facilities rely on the direct connection along this route both for

clients as well as hundreds of employees.

- E) Healthy Environment: The multi-modal enhancements previously mentioned along the corridor will provide residents first/last mile connections to the regional LRT system maximizing ridership potential. These improvements aim to invite more people to integrate walking, biking, and transit into their transportation routines. Project staff are working with the Bassett Creek Watershed Management. Commission to identify opportunities for storm drainage and storage enhancements.
- F) Leveraging Transportation Investments to Guide Land Use: This project enhances an already mature, medium-density neighborhood. The complimentary enhancements of this project, the Bassett Creek Regional Trail, and Bottineau LRT provide sustainable infrastructure for future investments in the area.

<sup>3.</sup> The project or the transportation problem/need that the project addresses must be in a local planning or programming document. Reference the name of the appropriate comprehensive plan, regional/statewide plan, capital improvement program, corridor study document [studies on trunk highway must be approved by the Minnesota Department of Transportation and the Metropolitan Council], or other official plan or program of the applicant agency [includes Safe Routes to School Plans] that the project is included in and/or a transportation problem/need that the project addresses.

- Hennepin County 2040 Bicycle Transportation
   Plan (Pg. 36)
- Three Rivers Park District Bassett Creek Regional Trail Master Plan (Pg. 40 to 41, 49 to 50, 60, 75)
- Bassett Creek Regional Trail CSAH 66 / Golden Valley Road Segment Feasibility Study (Full document)

List the applicable documents and pages:

- Golden Valley Comprehensive Plan (Pg. 7-29)
- METRO Blue Line Extension (Bottineau LRT)
   Station Area Planning: Plymouth Avenue and
   Golden Valley Road Stations (Pg.3-12 to 3-17)
- Metropolitan Council Regional Bicycle
   Transportation Network (Attachment 3.6)
- 4. The project must exclude costs for studies, preliminary engineering, design, or construction engineering. Right-of-way costs are only eligible as part of bicycle/pedestrian projects, transit stations/stops, transit terminals, park-and-ride facilities, or pool-and-ride lots. Noise barriers, drainage projects, fences, landscaping, etc., are not eligible for funding as a standalone project, but can be included as part of the larger submitted project, which is otherwise eligible.

#### Check the box to indicate that the project meets this requirement. Yes

5.Applicants that are not cities or counties in the seven-county metro area with populations over 5,000 must contact the MnDOT Metro State Aid Office prior to submitting their application to determine if a public agency sponsor is required.

#### Check the box to indicate that the project meets this requirement. Yes

6.Applicants must not submit an application for the same project elements in more than one funding application category.

#### Check the box to indicate that the project meets this requirement. Yes

7. The requested funding amount must be more than or equal to the minimum award and less than or equal to the maximum award. The cost of preparing a project for funding authorization can be substantial. For that reason, minimum federal amounts apply. Other federal funds may be combined with the requested funds for projects exceeding the maximum award, but the source(s) must be identified in the application. Funding amounts by application category are listed below.

Roadway Expansion: \$1,000,000 to \$7,000,000

Roadway Reconstruction/ Modernization: \$1,000,000 to \$7,000,000

Roadway System Management \$250,000 to \$7,000,000

**Bridges Rehabilitation/ Replacement:** \$1,000,000 to \$7,000,000

Check the box to indicate that the project meets this requirement. Yes

8. The project must comply with the Americans with Disabilities Act.

Check the box to indicate that the project meets this requirement. Yes

9. The project must be accessible and open to the general public.

Check the box to indicate that the project meets this requirement. Yes

10. The owner/operator of the facility must operate and maintain the project for the useful life of the improvement.

#### Check the box to indicate that the project meets this requirement. Yes

11. The project must represent a permanent improvement with independent utility. The term independent utility means the project provides benefits described in the application by itself and does not depend on any construction elements of the project being funded from other sources outside the regional solicitation, excluding the required non-federal match. Projects that include traffic management or transit operating funds as part of a construction project are exempt from this policy.

#### Check the box to indicate that the project meets this requirement. Yes

12. The project must not be a temporary construction project. A temporary construction project is defined as work that must be replaced within five years and is ineligible for funding. The project must also not be staged construction where the project will be replaced as part of future stages. Staged construction is eligible for funding as long as future stages build on, rather than replace, previous work.

#### Check the box to indicate that the project meets this requirement. Yes

13. The project applicant must send written notification regarding the proposed project to all affected state and local units of government prior to submitting the application.

Check the box to indicate that the project meets this requirement. Yes

## **Roadways Including Multimodal Elements**

1.All roadway and bridge projects must be identified as a Principal Arterial (Non-Freeway facilities only) or A-Minor Arterial as shown on the latest TAB approved roadway functional classification map.

Check the box to indicate that the project meets this requirement. Yes

#### Roadway Expansion and Reconstruction/Modernization projects only:

2. The project must be designed to meet 10-ton load limit standards.

Check the box to indicate that the project meets this requirement. Yes

#### Bridge Rehabilitation/Replacement projects only:

3.Projects requiring a grade-separated crossing of a Principal Arterial freeway must be limited to the federal share of those project costs identified as local (non-MnDOT) cost responsibility using MnDOTs Cost Participation for Cooperative Construction Projects and Maintenance Responsibilities manual. In the case of a federally funded trunk highway project, the policy guidelines should be read as if the funded trunk highway route is under local jurisdiction.

#### Check the box to indicate that the project meets this requirement.

4.The bridge must carry vehicular traffic. Bridges can carry traffic from multiple modes. However, bridges that are exclusively for bicycle or pedestrian traffic must apply under one of the Bicycle and Pedestrian Facilities application categories. Rail-only bridges are ineligible for funding.

#### Check the box to indicate that the project meets this requirement.

5. The length of the bridge must equal or exceed 20 feet.

#### Check the box to indicate that the project meets this requirement.

6. The bridge must have a sufficiency rating less than 80 for rehabilitation projects and less than 50 for replacement projects. Additionally, the bridge must also be classified as structurally deficient or functionally obsolete.

Check the box to indicate that the project meets this requirement.

#### **Requirements - Roadways Including Multimodal Elements**

## **Project Information-Roadways**

County, City, or Lead Agency Hennepin County

**Functional Class of Road** A-Minor Augmentor

**Road System CSAH** 

TH, CSAH, MSAS, CO. RD., TWP. RD., CITY STREET

Road/Route No. 66

i.e., 53 for CSAH 53

Name of Road Golden Valley Road

Example; 1st ST., MAIN AVE

Zip Code where Majority of Work is Being Performed 55422

(Approximate) Begin Construction Date 07/01/2021 (Approximate) End Construction Date 11/01/2022

TERMINI:(Termini listed must be within 0.3 miles of any work)

From:

100' west of Regent Avenue (Intersection or Address)

Bonnie Lane (Note: additional work may be needed to reach a

(Intersection or Address) logical project terminus)

DO NOT INCLUDE LEGAL DESCRIPTION

Or At

Grade, aggregate base, bituminous base and surfacing, curb **Primary Types of Work** 

and gutter, sidewalks, bike path, lighting, pedestrian ramps,

storm sewer, and signals.

Examples: GRADE, AGG BASE, BIT BASE, BIT SURF,

SIDEWALK, CURB AND GUTTER, STORM SEWER, SIGNALS, LIGHTING, GUARDRAIL, BIKE PATH, PED RAMPS,

BRIDGE, PARK AND RIDE, ETC.

**BRIDGE/CULVERT PROJECTS (IF APPLICABLE)** 

Old Bridge/Culvert No.:

New Bridge/Culvert No.:

Structure is Over/Under

(Bridge or culvert name):

## Expander/Augmentor/Connector/Non-Freeway Principal Arterial

Select one: Augmentor

0.993 Area

**Project Length** 0.932

**Average Distance** 1.0655

## Reliever: Relieves a Principal Arterial that is a Freeway Facility

Facility being relieved

Number of hours per day volume exceeds capacity (based on the Congestion Report)

## Reliever: Relieves a Principal Arterial that is a Non-Freeway Facility

Facility being relieved

Number of hours per day volume exceeds capacity (based on the table below)

## Non-Freeway Facility Volume/Capacity Table

Hour	NB/EB Volume	SB/WB Volume	Capacity	Volume exceeds capacity
12:00am - 1:00am			0	
1:00am - 2:00am			0	
2:00am - 3:00am			0	
3:00am - 4:00am			0	
4:00am - 5:00am			0	
5:00am - 6:00am			0	
6:00am - 7:00am			0	
7:00am - 8:00am			0	
8:00am - 9:00am			0	
9:00am - 10:00am			0	
10:00am - 11:00am			0	
11:00am - 12:00pm			0	
12:00pm - 1:00pm			0	
1:00pm - 2:00pm			0	
2:00pm - 3:00pm			0	
3:00pm - 4:00pm			0	
4:00pm - 5:00pm			0	
5:00pm - 6:00pm			0	
6:00pm - 7:00pm			0	
7:00pm - 8:00pm			0	

8:00pm - 9:00pm	0
9:00pm - 10:00pm	0
10:00pm - 11:00pm	0
11:00pm - 12:00am	0

## Measure B: Project Location Relative to Jobs, Manufacturing, and Education

Existing Employment within 1 Mile: 14078

Existing Manufacturing/Distribution-Related Employment within 1

Mile:

2096

Existing Students: 0

Upload Map 1466014330781\_CSAH66\_RegionalEconomy.pdf

## **Measure C: Current Heavy Commercial Traffic**

Location: CSAH 66, east of TH 100

Current daily heavy commercial traffic volume: 927

**Date heavy commercial count taken:** 05/17/2016 - 05/19/2016

## **Measure D: Freight Elements**

The CSAH 66 (Golden Valley Road) reconstruction project will modernize a 0.93 mile section of a 10ton roadway between Regent Avenue and Bonnie Lane in the City of Golden Valley. The improvements provide a new and structurally adequate roadway that can accommodate 2040 forecast traffic volumes. CSAH 66 is classified as an A-Minor Arterial that provides an essential eastwest connection near TH 100 between North Minneapolis and Golden Valley. Carrying 927 heavy commercial vehicles daily, this roadway provides a key alternate to TH 55 during periods of construction or congestion. Among other purposes, this roadway provides a direct route for medical and other supply deliveries to the Courage-Kenny Rehabilitation Institute. Additionally, the Golden Valley Fire Station #3 is located directly on CSAH 66, which depends on a direct, continuous, and structurally sound roadway for emergency response vehicles.

Response (Limit 1,400 characters; approximately 200 words)

Additional improvements to facilitate freight movements and improve overall safety and efficiency along the corridor include, but are not limited to:

- Convert an unwarranted all-way stop at CSAH 66 and Regent Avenue to a two-way stop control intersection
- Provide flashing yellow arrows at all signalized intersections
- Reconfigure striping and install turn lanes
- Replace existing curb and gutter, and construct new curb and gutter where missing for improved roadway definition

Location West of Noble Avenue

16500 **Current AADT Volume** 

**Existing Transit Routes on the Project** 14, 758

For New Roadways only, list transit routes that will be moved to the new roadway

**Upload Transit Map** 1466439770953\_CSAH66\_TransitConnections.pdf

## **Response: Current Daily Person Throughput**

**Average Annual Daily Transit Ridership** 

**Current Daily Person Throughput** 21450.0

#### Measure B: 2040 Forecast ADT

Use Metropolitan Council model to determine forecast (2040) ADT Yes volume

If checked, METC Staff will provide Forecast (2040) ADT volume

**OR** 

Identify the approved county or city travel demand model to determine forecast (2040) ADT volume

Forecast (2040) ADT volume

## Measure A: Project Location and Impact to Disadvantaged Populations

#### Select one:

Project located in Area of Concentrated Poverty with 50% or more of residents are people of color (ACP50):

**Project located in Area of Concentrated Poverty:** 

Projects census tracts are above the regional average for population in poverty or population of color:

Project located in a census tract that is below the regional average for population in poverty or populations of color or includes children, people with disabilities, or the elderly:

Yes

When complete, this project will achieve a safe and inviting corridor for all ages, physical abilities, and travel modes. The project greatly enhances connectivity and safety, specifically for the elderly and disabled by constructing ADA compliant pedestrian ramps, Accessible Pedestrian Signals (APS), durable crosswalk markings, pedestrian median islands, and countdown timers. Considering the existing bus service along this corridor as well as the planned Bottineau LRT Station, pedestrian enhancements and ADA features are critical to ridership. These first/last mile improvements are especially beneficial in relation to the medical facilities at Hidden Lakes Parkway including Courage Kenny Rehabilitation Institute which has numerous clients with disabilities.

Response (Limit 2,800 characters; approximately 400 words)

The CSAH 66 Reconstruction Project is located in a census tract that is below the regional average for population in poverty or populations of color. The CSAH 66 Reconstruction Project will not have an adverse effect on populations in poverty or populations of color. This project will maintain a vital link between Minneapolis and western suburban communities.

The area of Minneapolis to the immediate east of the project is an area of concentrated poverty with 50% or more residents being people of color. CSAH 66 provides a vital link to employment and services for people living in this area.

The response should address the benefits, impacts, and mitigation for the populations affected by the project.

**Upload Map** 

 $1466086677453\_CSAH66\_SocioEconomic.pdf$ 

#### Measure B: Affordable Housing

City/Township

**Segment Length in Miles (Population)** 

City of Golden Valley

Τ	otal	Pro	iect	Len	ath

**Total Project Length (Total Population)** 

0.93

## Affordable Housing Scoring - To Be Completed By Metropolitan Council Staff

**Housing Score** Segment **Total Length Multiplied** by Segment City/Township Score Length/Total Length (Miles) **Segment** (Miles) Length percent 0 0 0 0

## Affordable Housing Scoring - To Be Completed By Metropolitan Council Staff

Total Project Length (Miles)

0.93

**Total Housing Score** 

0

## Measure A: Year of Roadway Construction

**Year of Original** 

Calculation 2	Calculation	Segment Length	or Most Recent Reconstruction
591.011	549.64	0.28	1963
1363.602	1268.15	0.65	1951
1955	1818	1	

### **Average Construction Year**

Weighted Year 1954

## **Total Segment Length (Miles)**

Total Segment Length 0.93

### Measure B: Geometric, Structural, or Infrastructure Improvements

Improving a non-10-ton roadway to a 10-ton roadway:

Yes

pavement structure given its State Aid designation. The paved shoulders exhibit significant settlement due to poor stormwater drainage caused by poor condition of the existing stormwater structures and lack of concrete curb and gutter. Over the years heavy commercial truck traffic has caused Response (Limit 700 characters; approximately 100 words) significant deterioration to the roadway to the point where maintenance activities offer little to no benefit in improving the pavement. The project will install concrete curb and gutter along the entire corridor defining the roadway limits and separating the vehicle facilities from the bicycle and pedestrian facilities. Improved clear zones or sight lines: Yes Sight lines will be improved for vehicles traveling southbound on Regent Avenue, looking east on CSAH 66. The horizontal curve at this location will be improved to meet a design speed of 35 mph. In Response (Limit 700 characters; approximately 100 words) addition, new sidewalk and boulevard on the north side of CSAH 66 will allow for better sight lines by removing some existing landscaping near the edge of the roadway. Improved roadway geometrics: Yes The existing four-lane undivided section between Regent Avenue and Noble Avenue will be restriped as a three-lane section with a two-way left turn lane to allow for safer local street and driveway access by separating turning vehicles from through traffic. Response (Limit 700 characters; approximately 100 words) New dedicated eastbound and westbound left-turn lanes on CSAH 66 at Regent Avenue will be properly aligned to eliminate the negative offset of the existing condition. Dedicated southbound right and left-turn lanes will be striped on Noble Avenue approaching CSAH 66 to clarify lane usage. Access management enhancements: Yes

Golden Valley Road is currently provides a 10-ton

undivided roadway to a 3-lane section with a shared left turn lane to improve access and safety throughout the residential area. Golden Valley Road serves as a major east/west through corridor to bypass TH 55, so a majority of the vehicles do Response (Limit 700 characters; approximately 100 words) not turn into the side streets. Therefore, a 3-lane section will provide a dedicated space for leftturning vehicles to improve comfort and safety for drivers. The Golden Valley Road Project will also install concrete curb and gutter which will better define the roadway to reduce confusion on where access points are located. Vertical/horizontal alignments improvements: Yes Horizontal improvement: Currently a 30 mph speed advisory is posted for westbound vehicles Response (Limit 700 characters; approximately 100 words) approaching Regent Avenue. This curve will be revised to meet a 35 mph design speed, consistent with the remainder of the roadway. Improved stormwater mitigation: Yes The project is within the boundaries of the Bassett Creek Watershed Management Commission (BCWMC) and adjacent to Sweeney Lake (27-0035). Sweeney Lake (listed as impaired for nutrients and chlorides) has an approved TMDL and as a result, the county has an associated waste load allocation for phosphorus. Response (Limit 700 characters; approximately 100 words) While the county will meet all of the watershed's stormwater management rules triggered by the project, the county has already initiated conversations with the BCWMC to research opportunities to partner on additional stormwater BMPs (i.e., stormwater reuse for irrigation on public parcels) to go beyond compliance and get more stormwater volume and associated nutrient load

reductions.

Yes

Signals/lighting upgrades:

The roadway section between Regent Avenue and

Noble Avenue will be converted from a 4-lane

Response (Limit 700 characters; approximately 100 words)

Other Improvements

Response (Limit 700 characters; approximately 100 words)

Existing traffic signals at Noble Avenue and Hidden Lakes Parkway will be upgraded to meet current signal and ADA design standards. All signals will include yellow flashing arrows for improved left turn operation. Traffic signal luminaires will be upgraded with new lighting, and additional lighting will be installed throughout the corridor to provide a more comfortable and inviting environment for sidewalk and trail users.

Yes

Traffic calming elements will encourage drivers to abide by the posted speed limit and result in a more inviting and attractive corridor:

- Narrowing travel lanes to 11 feet
- Creating a boulevard space between the roadway and trail or sidewalk with vertical elements including landscaping, lighting, signs, and other streetscaping elements that will help visually narrow the roadway
- Improving safety at pedestrian crossings
- Adding of a regional trail connection and improved sidewalk connections
- Enhancing placemaking treatments at key gateway locations along the corridor, including signalized intersections

**EXPLANATIO** 

## Measure A: Congestion Reduction/Air Quality

Total Peak Hour Delay Per Vehicle Without The Project	Total Peak Hour Delay Per Vehicle With The Project	Total Peak Hour Delay Per Vehicle Reduced by Project	Volume (Vehicles per hour)	Total Peak Hour Delay Reduced by the Project:	N of methodology used to calculate railroad crossing delay, if	Synchro or HCM Reports
					applicable.	

14685072574 21\_CSAH 66 -7.0 17.0 1546 26282.0 Congestion Reduction -Regent.pdf

## **Total Delay**

24.0

**Total Peak Hour Delay Reduced** 

26282.0

# Measure B:Roadway projects that do not include new roadway segments or railroad grade-separation elements

3	1		1546	2489
2.88	1.27	1.61	1546.0	2489.06
Total (CO, NOX, and VOC) Peak Hour Emissions Per Vehicle without the Project (Kilograms):	Total (CO, NOX, and VOC) Peak Hour Emissions Per Vehicle with the Project (Kilograms):	Total (CO, NOX, and VOC) Peak Hour Emissions Reduced Per Vehicle by the Project (Kilograms):	Volume (Vehicles Per Hour):	Total (CO, NOX, and VOC) Peak Hour Emissions Reduced by the Project (Kilograms):

#### **Total**

**Total Emissions Reduced:** 

2489.06

**Upload Synchro Report** 

1468507336625\_CSAH 66 - Congestion Reduction - Regent.pdf

# Measure B: Roadway projects that are constructing new roadway segments, but do not include railroad grade-separation elements (for Roadway Expansion applications only):

Total (CO, NOX, Total (CO, NOX, Total (CO, NOX, Total (CO, NOX, and VOC) Peak and VOC) Peak and VOC) Peak and VOC) Peak **Hour Emissions Hour Emissions Hour Emissions Volume (Vehicles Hour Emissions Reduced Per** Reduced by the Per Vehicle Per Vehicle with Per Hour): Vehicle by the without the Project the Project **Project Project** (Kilograms): (Kilograms): (Kilograms): (Kilograms):

0 0 0

## **Emissions Reduced on Parallel Roadways** 0 **Upload Synchro Report New Roadway Portion:** Cruise speed in miles per hour with the project: 0 Vehicle miles traveled with the project: 0 Total delay in hours with the project: 0 Total stops in vehicles per hour with the project: 0 Fuel consumption in gallons: Total (CO, NOX, and VOC) Peak Hour Emissions Reduced or 0 Produced on New Roadway (Kilograms): **EXPLANATION** of methodology and assumptions used:(Limit 1,400 characters; approximately 200 words) Total (CO, NOX, and VOC) Peak Hour Emissions Reduced by the 0.0 Project (Kilograms):

## Measure B:Roadway projects that include railroad grade-separation elements

Cruise speed in miles per hour without the project:	0
Vehicle miles traveled without the project:	0
Total delay in hours without the project:	0
Total stops in vehicles per hour without the project:	0
Cruise speed in miles per hour with the project:	C
Vehicle miles traveled with the project:	C
Total delay in hours with the project:	C
Total stops in vehicles per hour with the project:	C
Fuel consumption in gallons (F1)	0
Fuel consumption in gallons (F2)	0
Fuel consumption in gallons (F3)	C
Total (CO, NOX, and VOC) Peak Hour Emissions Reduced by the Project (Kilograms):	C
EXPLANATION of methodology and assumptions used:(Limit	

**Total Parallel Roadways** 

1,400 characters; approximately 200 words)

If the applicant is completing a transit or TDM application that is operations only, check the box and do not complete the remainder of the form. These projects will receive full points for the Risk Assessment.

Park-and-Ride and other transit construction projects require completion of the Risk Assessment below.

**Check Here if Your Transit Project Does Not Require Construction** 

Measure A: Risk Assessment		
1)Project Scope (5 Percent of Points)		
Meetings or contacts with stakeholders have occurred	Yes	
100%		
Stakeholders have been identified		
40%		
Stakeholders have not been identified or contacted		
0%		
2)Layout or Preliminary Plan (5 Percent of Points)		
Layout or Preliminary Plan completed		
100%		
Layout or Preliminary Plan started	Yes	
50%		
Layout or Preliminary Plan has not been started		
0%		
Anticipated date or date of completion	05/07/2018	
3)Environmental Documentation (5 Percent of Points)		
EIS		
EA	Yes	
РМ		
Document Status:		
Document approved (include copy of signed cover sheet)	100%	
Document submitted to State Aid for review	75%	date submitted
Document in progress; environmental impacts identified; review request letters sent		
50%		
Document not started	Yes	
0%		
Anticipated date or date of completion/approval	07/01/2019	

#### 4) Review of Section 106 Historic Resources (10 Percent of Points)

No known historic properties eligible for or listed in the National Register of Historic Places are located in the project area, and project is not located on an identified historic bridge

Yes

100%

Historic/archeological review under way; determination of no historic properties affected or no adverse effect anticipated

80%

Historic/archaeological review under way; determination of adverse effect anticipated

40%

Unsure if there are any historic/archaeological resources in the project area

0%

Anticipated date or date of completion of historic/archeological review:

03/04/2019

Project is located on an identified historic bridge

#### 5) Review of Section 4f/6f Resources (10 Percent of Points)

4(f) Does the project impacts any public parks, public wildlife refuges, public golf courses, wild & scenic rivers or public private historic properties?6(f) Does the project impact any public parks, public wildlife refuges, public golf courses, wild & scenic rivers or historic property that was purchased or improved with federal funds?

No Section 4f/6f resources located in the project area

100%

No impact to 4f property. The project is an independent bikeway/walkway project covered by the bikeway/walkway Negative Declaration statement; letter of support received

100%

Section 4f resources present within the project area, but no known adverse effects

Yes

80%

Project impacts to Section 4f/6f resources likely coordination/documentation has begun

50%

Project impacts to Section 4f/6f resources likely coordination/documentation has not begun

30%

Unsure if there are any impacts to Section 4f/6f resources in the project area

0%

6)Right-of-Way (15 Percent of Points)

Right-of-way, permanent or temporary easements not required

100%	

Right-of-way, permanent or temporary easements has/have been acquired

100%

Right-of-way, permanent or temporary easements required, offers made

75%

Right-of-way, permanent or temporary easements required, appraisals made

50%

Right-of-way, permanent or temporary easements required, parcels identified

Yes

25%

Right-of-way, permanent or temporary easements required, parcels not identified

0%

Right-of-way, permanent or temporary easements identification has not been completed

0%

Anticipated date or date of acquisition

03/02/2020

7)Railroad Involvement (25 Percent of Points)

No railroad involvement on project

Yes

100%

Railroad Right-of-Way Agreement is executed (include signature page)

100%

Railroad Right-of-Way Agreement required; Agreement has been initiated

60%

Railroad Right-of-Way Agreement required; negotiations have begun

40%

Railroad Right-of-Way Agreement required; negotiations not begun

0%

**Anticipated date or date of executed Agreement** 

11/04/2019

#### 8)Interchange Approval (15 Percent of Points)\*

\*Please contact Karen Scheffing at MnDOT (Karen.Scheffing@state.mn.us or 651-234-7784) to determine if your project needs to go through the Metropolitan Council/MnDOT Highway Interchange Request Committee.

Project does not involve construction of a new/expanded interchange or new interchange ramps

Yes

100%

Interchange project has been approved by the Metropolitan Council/MnDOT Highway Interchange Request Committee

100%

Interchange project has not been approved by the Metropolitan Council/MnDOT Highway Interchange Request Committee

0%

9)Construction Documents/Plan (10 Percent of Points)

Construction plans completed/approved (include signed title sheet)

100%

Construction plans submitted to State Aid for review

75%

Construction plans in progress; at least 30% completion

50%

Construction plans have not been started

Yes

0%

Anticipated date or date of completion 03/02/2020

10)Letting

Anticipated Letting Date 06/01/2020

## Measure A: Roadway Projects that do not Include Railroad Grade-Separation Elements

**Crash Modification Factor Used:** 

39.0

The following is a list of Crash Modification Factors accessed from the CMF Clearinghouse database. Multiple CMF's were applied to each crash since the CSAH 66 Reconstruction Project will include multiple improvements to address safety. The overall average crash reduction expected is 61%, based on a 39% crash modification factor.

Improvement type (CMF ID, crash reduction)

- 01) Increased pavement friction all crashes (CMF 194, 24%)
- 02) Increased pavement friction wet pavement (CMF 195, 57%)
- 03) Increased pavement friction rear end crashes (CMF 197, 42%)
- 04) Increased pavement friction single vehicle crashes (CMF 198, 30%)
- 05) Narrow cross section from 4 to 3 lanes (CMF 874, 37%)
- 06) Coordinated signal timing (CMF 3072, 83%)
- 07) Convert unwarranted all-way stop to two-way stop. This project is proposing removal of an unwarranted all-way stop at CSAH 66 and Regent Avenue. Logically, rear end crashes on CSAH 66 at Regent will be eliminated. (100% reduction for these types of crashes).

(Limit 1400 Characters; approximately 200 words)

**Rationale for Crash Modification Selected:** 

Project Benefit (\$) from B/C Ratio

**Worksheet Attachment** 

\$3,436,297.00

1468508343734\_CSAH 066 (Golden Valley Rd) Reconstruction - Benefit Cost Worksheets.pdf

Roadway projects that include railroad grade-separation elements:

Current AADT volume:	0
Average daily trains:	0
Crash Risk Exposure eliminated:	0

# **Measure A: Multimodal Elements and Existing Connections**

This segment of CSAH 66 (Golden Valley Road) transitions from an undivided four-lane roadway at Regent Avenue to a two-lane roadway with turn lanes at signalized intersections east of Noble Avenue to the project termini at Bonnie Lane. Sidewalks are present on both sides of the corridor in most locations, but critical gaps and deteriorating conditions make them difficult to navigate. Existing shoulders were recently painted as bicycle lanes east of Noble Avenue.

The CSAH 66 reconstruction project will provide the following multimodal elements (subject to approval by the Golden Valley City Council):

Response (Limit 2,800 characters; approximately 400 words)

- Replace the existing sidewalks, fill gaps in the sidewalk network, and relocate obstructing utilities
- Upgrade crossings and intersections with ADAcompliant pedestrian ramps, pedestrian crossing islands, and Accessible Pedestrian Signals (APS) with countdown timers
- Construct a shared-use Bassett Creek Regional
   Trail segment for the full project length
- Provide a planted boulevard with streetscaping elements
- Improve transit access, amenities, and circulation for existing routes and a planned LRT station

CSAH 66 is identified as a planned off-street bikeway in the county bicycle plan and as the preferred alignment for the Three Rivers Park District's Bassett Creek Regional Trail (BCRT). The dilapidated and incomplete sidewalk will be replaced with a new regional trail connection (BCRT) on the south side of the roadway, and continuous concrete sidewalk on the north side

(pending city council approval). ADA-compliant pedestrian ramps will be installed at all crossings, and signalized intersections will be upgraded to include ADA-compliant signals with countdown timers. A planted boulevard will further enhance the corridor for all users, adding green space, calming traffic, providing a buffer between sidewalk/trail users and motorized traffic, and creating space for improved lighting, streetscaping, and transit stop improvements.

Metro Transit routes 14 and 758 currently serve the corridor. Sidewalk, trail, boulevard, and crossing improvements will provide immediate and direct benefits to transit users. Context-sensitive improvements to the Courage Kenny Rehabilitation Institute transit stop will benefit riders who are more likely to experience mobility limitations. The Metro Blue Line Extension is also planned within a quarter mile of the project, including a station at Golden Valley Road and Theodore Wirth Parkway. This project implements improvements specified in previous station area plans, which call for improved pedestrian and bicycle access to Golden Valley Station. Final connections between this project and Golden Valley Station and the Minneapolis Grand Rounds will be implemented in coordination with Blue Line Extension construction.

#### **Measure A: Cost Effectiveness**

Total Project Cost (entered in Project Cost Form): \$8,761,000.00

Enter Amount of the Noise Walls: \$0.00

Total Project Cost subtract the amount of the noise walls: \$8,761,000.00

**Points Awarded in Previous Criteria** 

Cost Effectiveness \$0.00

#### Other Attachments

File Name	Description	File Size
Attachment 1.1 - Hennepin County - Project Map.pdf	Project area map for CSAH 66 reconstruction	628 KB
Attachment 1.2 - Hennepin County - Typical Sections.pdf	Typical sections for CSAH 66 reconstruction	226 KB
Attachment 1.3 - Hennepin County - Concept.pdf	Attachment 1.3 - Concept	116.5 MB
Attachment 2.1 - City of Golden Valley - Letter of Support.pdf	City of Golden Valley letter of support for CSAH 66 reconstruction	804 KB
Attachment 2.2 - Three Rivers Park District - Letter of Support.pdf	Three Rivers Park District letter of support for CSAH 66 reconstruction	213 KB
Attachment 3.1 - Hennepin County - Planned Bikeway System Map.pdf	Hennepin County Planned Bikeway System Map, project area identified as off street bikeway	1.9 MB
Attachment 3.2 - Three Rivers Park District - BCRT Master Plan - Golden Valley Segment.pdf	Three Rivers Park District Bassett Creek Regional Trail Master Plan, Golden Valley Segment	1.0 MB
Attachment 3.3 - City of Golden Valley - BCRT Feasibility Study Alignment.pdf	City of Golden Valley Bassett Creek Regional Trail Feasibility Study, Trail Alignment	395 KB
Attachment 3.4 - City of Golden Valley - Comprehensive Plan - Ped Bike Network.pdf	City of Golden Valley Comprehensive Plan, Pedestrian and Bicycle Network	890 KB
Attachment 3.5 - METRO Transit - Blue Line Ext - Station Area Planning.pdf	METRO Transit Blue Line Extension Station Area Planning, Golden Valley Station Circulation and Streetscaping Improvements	380 KB
Attachment 3.6 - Metropolitan Council - Regional Bicycle Transportation Network.pdf	CSAH 66 project area identified as a Tier 2 corridor in Metropolitan Council's Regional Bicycle Transportation Network (RBTN)	369 KB
Attachment 4.1 - Hennepin County - Traffic Volumes.pdf	2016 Hennepin County Traffic Volume Data, AADT, CSAH 66 and East of T.H. 100	51 KB
Attachment 4.2 - Hennepin County - Heavy Vehicle Volumes.pdf	2016 Hennepin County Traffic Volume Data, Heavy Vehicle Traffic, CSAH 66 and East of T.H. 100	60 KB
Attachment 4.3 - CSAH 66 2040 Forecasts from Mark Filipi.pdf	2040 Traffic Volume Forecasts from Mark Filipi	96 KB
Attachment 4.4 - Hennepin County - Turning Movement Counts.pdf	2016 Hennepin County Turning Movement Counts - CSAH 66 & Regent Ave	121 KB


Attachment 5.1 - MnDOT - 2013-2015 Crash Data.pdf	2013-2015 crash data provided by MnDOT	656 KB
Attachment 5.2 - CMF Clearinghouse - CSAH 66 Crash Modification Factors.pdf	CMF Clearinghouse details used for cost/benefit analysis	254 KB
Attachment 5.3 - CMF Clearinghouse - CSAH 66 Crash Modification Factors.pdf	Crash Modification Factors applied to CSAH 66 2013-2015 collisions	277 KB
Attachment 6 - Hennepin County - Risk Assessment Notes.pdf	Risk Assessment Notes	65 KB

# Roadway Area Definition

Results

Project Length: 0.932 miles

Project Area: 0.993 sq mi







0 1 2 4 6 8 Miles


Created: 6/13/2016 LandscapeRSA1











Direction	All
Volume (vph) Total	1546
Delay / Veh (s/v)	24
CO Emissions (kg)	2.02
NOx Emissions (kg)	0.39
VOC Emissions (kg)	0.47

Direction	All	
Volume (vph) Total	1536	
Delay / Veh (s/v)	7	
CO Emissions (kg)	0.89	
NOx Emissions (kg)	0.17	
VOC Emissions (kg)	0.21	

Direction	All
Volume (vph) Total	1546
Delay / Veh (s/v)	24
CO Emissions (kg)	2.02
NOx Emissions (kg)	0.39
VOC Emissions (kg)	0.47

Direction	All	
Volume (vph) Total	1536	
Delay / Veh (s/v)	7	
CO Emissions (kg)	0.89	
NOx Emissions (kg)	0.17	
VOC Emissions (kg)	0.21	

B/works				T.H. / Roadway  CSAH 66	Conve	gent Ave	<b>Location</b> on to Two	Ending Ref. Pt.  0.86 tering Judgement	State, County, City or Township Hennepin County	Study Period Begins	Study Period Ends					
				cription of osed Work	Conve	ert CSAH 66	to 3-lane	section with a	TWLTL (CM)	F ID 2	2841)					
Accid	ent Dia	gram Codes	1	<b>&gt;-&gt;</b>	2	ise pavement	3	✓ I	5	4, 7		8,9	Pedestrian	6, 90, 98, 99 Other	Total	
	Fatal	Ŀ														
		F A														
Study Period: Number of	Personal Injury (PI)	С		1											1	
Crashes	Property P			1										1	2	
% Change in Crashes	nge F													1	_	
	PI D															
*Use FHWA cmfclearingho use for Crash		С		-100%												
Reduction Factors	Property Damage			-100%										-57%		
	Fatal	F														
		A														
Change in Crashes	PI	В														
= No. of		С		-1.00											-1.00	
crashes <b>X</b> % change in crashes	Property Damage	PD		-1.00										-0.57	-1.57	
Year (Safety I	mprov	ement	Construct	ion)		2020										
Project Cost	Project Cost (exclude Right of Way) \$ 8,461,00						Type of Crash	Study Period: Change in Crashes	Annual Change in Crashes	Cos	t per Crash	Annual Benefit		B/C=	0.07	
Right of Way	y Cost	s (opt	ional)				F			\$	1,140,000		Using present	worth value	?S,	
Traffic Grow	th Fa	ctor				3%	A			\$	570,000		<b>B</b> =	\$	554,084	
Capital Reco	very						В			\$	170,000		C=		461,000	
1. Discoun	1. Discount Rate 4.5%					C	-1.00	-0.33	\$	83,000	\$ 27,692	See "Calculat amortization.	ions sheet f	or		
2. Project Service Life (n) 20					PD	-1.57	-0.52	\$	7,600	\$ 3,981						
							Total \$ 31,673									

-

Canal Cana		worksheet			T.H. / Roadway			Location			Beginni Ref. Pt		Ending Ref. Pt.	State, County, City or Township	Study Period Begins	Study Period Ends
Proposed Work   Proposed Wor				Des	•								1.14		1/1/2013	12/31/2015
Study   Period:				Prop	osed Work	Conve	ert CSAH 66	to 3-lane	section with	FWLTL (CM)						
Sindy   Period:   Sindy   Si	Accid			1		2		3		5	4, 7		8, 9		6, 90, 98, 99	
Sindy   Period:   Sindy   Si									<b>←</b>	•			<b>-</b>	Pedestrian	Other	Total
Study   Freid:   Study   Freid:   Study   St		_				_	<b>_</b>				¥		<b>→</b>			
Second   S		Fatal	F													
Second   S		, (PI)	A													
Second   S		Injury														
Second   S		rsonal	В													
State   Figure   State   Sta	Crashes															
No.   Project Cost   Exclusion   Project Cost   Exclusion   English of Way)   S. 8,956,000   S. 8,956,000   S. 1,140,000   S. 1,140,141   S		Propert Damag	PD				1									1
No.   Project Cost   Exclusion   Project Cost   Exclusion   English of Way)   S. 8,956,000   S. 8,956,000   S. 1,140,000   S. 1,140,141   S	% Change	Fatal	F													
Project Cost (exclude Right of Way)   Project Service Life (n)   Pr																
Table   Tabl		Jse FHWA offclearingho														
Reduction   Factors   Fa																
Table   F   F   F   F   F   F   F   F   F		20 0														
Table   F   F   F   F   F   F   F   F   F	<u>Factors</u>	Propert Damag	PD				-37%									
Change in Crashes   Pi																
Pi																
No. of crashes   No.	Change in	DI														
Crashes X   % change in   Crashes   Cost per Crash   Crashes   Cost per C	Crashes	11	В													
Note   Continue   Construction   C	crashes X	rty age														
Study   Period:   Change in   Crashes   Cost per Crash   Benefit	% change in crashes	Prope Dama	PD				-0.37									-0.37
Project Cost (exclude Right of Way)	Year (Safety l	mprove	ement	Constructi	ion)		2020									
Type of Change in Change in Crashes   Cost per Crash   Breefit										٨ ١						
Right of Way Costs (optional)   F   \$ 1,140,000   Using present worth values,   B   \$ 570,000   B = \$ 16,413									Change in	Change in					B/C=	0.00
Traffic Growth Factor         3%         A         \$ 570,000         B         \$ 170,000         B         \$ 170,000         C= \$ 8,956,000           1. Discount Rate         4.5%         C         \$ 83,000         See "Calculations" sheet for amortization.           2. Project Service Life (n)         20         PD         -0.37         -0.12 \$ 7,600 \$ 938	Project Cost	roject Cost (exclude Right of Way) \$ 8,956,000					8,956,000	Crash	Crashes	Crashes	Cost per C	Crash	Benefit			
Capital Recovery         B         \$ 170,000         C=\$ 8,956,000           1. Discount Rate         4.5%         C         \$ 83,000         See "Calculations" sheet for amortization.           2. Project Service Life (n)         20         PD         -0.37         -0.12         \$ 7,600         \$ 938	Right of Way							F			\$ 1,14	0,000				
1. Discount Rate 4.5% C \$ 83,000 See "Calculations" sheet for amortization.  2. Project Service Life (n) 20 PD -0.37 -0.12 \$ 7,600 \$ 938	Traffic Grow	th Fa	ctor				3%	A			\$ 57	0,000				•
1. Discount Rate         4.5%         C         \$ 83,000         amortization.           2. Project Service Life (n)         20         PD         -0.37         -0.12         \$ 7,600         \$ 938	Capital Reco	Capital Recovery					В			\$ 17	0,000					
Total	1. Discount Rate 4.5%				C			\$ 8	3,000			ons" sheet f	or			
Total	2. Project Service Life (n) 20				PD	-0.37	-0.12	\$	<b>7,6</b> 00	\$ 938						
N 95X I	•					Total					\$ 938					


-

	B/C Control Section Records						Location			Beginnir Ref. Pt		Ending Ref. Pt.	State, County, City or Township	Study Period Begins	Study Period Ends
						dden Lakes I				1.47		1.53	Hennepin County	1/1/2013	12/31/2015
			Des Prop	scription of osed Work	Imple Impro	ment traffic	signal coo t friction -	rdination alon rear end cras	g arterial road hes (CMF ID	lway (CMF II 197)	D 3072	2)			
Accid		gram Codes	1		2		3		5	4, 7		8, 9		6, 90, 98, 99	
	\	/	<b> </b>	<b>&gt;-&gt;</b>	_	<b>→</b>	9	<b>←</b>				<b></b>	Pedestrian	Other	Total
	Fatal	F													
		A													
Study Period:	Personal Injury (PI)	В													
Number of Crashes	Person	С													
	Property Damage	PD		2											2
% Change	Fatal D	F													L
in Crashes	I	A													
*Use FHWA	Use FHWA nfclearingho														
cmfclearingho use for Crash															
Reduction Factors	Property Damage	PD		-91%											
	Fatal D	F		-9170											
	1	A													
Change in Crashes	PI	В													
= No. of		С													
crashes <b>X</b> % change in crashes	Property Damage	PN		-1.82											-1.82
Year (Safety I			Construct			2020									1.02
Project Cast	roject Cost (exclude Right of Way) \$ 8,761,00							Study Period: Change in Crashes	Annual Change in Crashes	Cost per C	roch	Annual Benefit		B/C=	0.01
	Right of Way Costs (optional)						Crash F	Crasiles	Crasiles	_	0,000	Bellefit	Using present	worth value	25
Traffic Grow						3%	A				0,000		B=		80,732
Capital Reco	Capital Recovery						В			\$ 170	0,000		C=		761,000
1. Discount Rate 4.5%					С			\$ 83	3,000		See "Calculat amortization.	ions" sheet f	or		
2. Project Service Life (n) 20					PD -1.82 -0.61 \$				7,600	\$ 4,615	5				
							Total					\$ 4,615			

-


B/ works			Control Section	T.H. / Roadway		Location				Beginning Ref. Pt.	Ending Ref. Pt.	State, County, City or Township	Study Period Begins	Study Period Ends
				CSAH 66	West of Noble Av	enue				0.86	1.08	Hennepin County	1/1/2013	12/31/2015
				scription of osed Work	Increase navement	friction - friction - friction -	rear end crash all crashes (C wet pavemen	nes (CMF ID MF ID 194) t crashes (CM	197) ⁄/F II	) D 195)				
Accide	ent Dia	gram Codes	1		2	3		5	4, 7		8, 9		6, 90, 98, 99	
	\		<b>—</b>	<b></b>		9		<del>_</del>			<b>*</b>	Pedestrian	Other	Total
	Fatal	F												
	y (PI)	A												
Study Period:	Personal Injury (PI)	В											1	1
Number of Crashes	Person	С											1	1
	Property Damage	PD		1			1							2
% Change	Fatal D	F		1			1							Z
in Crashes		A												
*Use FHWA	PI	В											-56%	
cmfclearingho use for Crash		С											-73%	
Reduction Factors	Property Damage	PD		-63%		-52%								
	Fatal	F												
		A												
Change in Crashes	PI	В											-0.56	-0.56
= No. of		C											-0.73	-0.73
crashes <b>X</b> % change in	Property Damage	DD.		0.62			0.53							1 15
crashes  Vear (Safety I			Construct	-0.63	2020		-0.52							-1.15
	(ear (Safety Improvement Construction) 202  Project Cost (exclude Right of Way) \$ 8,761,000						Study Period: Change in Crashes	Annual Change in Crashes	Co	ost per Crash	Annual Benefit		B/C=	0.11
Right of Way	Right of Way Costs (optional)								\$	1,140,000		Using present	worth value	'S.
Traffic Grow					3%	F A			\$	570,000		<b>B</b> =		960,302
Capital Reco	very					В	-0.56	-0.19	\$	170,000	\$ 31,762	C=		761,000
1. Discount Rate 4.5%					C	-0.73	-0.24	\$	83,000	\$ 20,215	See "Calculat amortization.	ions" sheet f	or	
2. Project Service Life (n) 20					PD	-1.15	-0.38	\$	7,600	\$ 2,916				
						Total	Total \$ 54,893							

B/ works			Control Section	T.H. / Roadway			Location				eginning Ref. Pt.	Ending Ref. Pt.	State, County, City or Township	Study Period Begins	Study Period Ends
				CSAH 66 cription of osed Work	Increa		friction -	rear end crass			1.14 195)	1.78	Hennepin County	1/1/2013	12/31/2015
Accid	ent Dia	gram Codes	_	oscu Work	Incras 2	e pavement	friction - s	ingle vehicle	crashes (CMI 5	F ID 1	98)	8, 9		6, 90, 98, 99	
			<b>—</b>	<b></b>	=	<b>→</b>					7	<b>*</b>	Pedestrian	Other	Total
	) Fatal	F													
Study Period: Number of	Personal Injury (PI)	A B										1		1	1
Crashes	Property Pe	С		1							2				1
0/ ()	Fatal D	PD F		1							2				3
% Change in Crashes	I	A												-30%	
*Use FHWA	PI	В										-57%		-3070	
cmfclearingho use for Crash		C		-42%								67,70			
Reduction Factors	Property Damage	PD		-42%							-44%				
	Fatal	F													
		A												-0.30	-0.30
Change in Crashes	PI	В										-0.57			-0.57
= No. of crashes <b>X</b>	> 0	С		-0.42											-0.42
% change in crashes	Property Damage	PD		-0.42							-0.88				-1.30
Year (Safety I	mprove	ement	Constructi	ion)		2020		<i>a.</i> •		1			i		
Project Cost	Project Cost (exclude Right of Way) \$ 8,761,00							Study Period: Change in Crashes	Annual Change in Crashes	Cos	t per Crash	Annual Benefit		B/C=	0.21
Right of Way	Right of Way Costs (optional)						F			\$	1,140,000		Using present	worth value	s,
Traffic Grow	th Fa	ctor				3%	A	-0.30	-0.10	\$	570,000	\$ 57,052	В=		824,766
Capital Reco	very						В	-0.57	-0.19	\$	170,000	\$ 32,330	<b>C=</b> See "Calculat		761,000
1. Discoun	1. Discount Rate 4.5%					4.5%	С	-0.42	-0.14	\$	83,000	\$ 11,631	amortization.	sneet j	
2. Project Service Life (n) 20					20	PD -1.30 -0.43 \$ 7,600			\$ 3,296						
							Total					\$ 104,309			



## **CSAH 66 (Golden Valley Road) Reconstruction**

Typical Sections - Widths Vary



EAST OF NOBLE AVENUE

| Sidewalk | boulevard | travel lane | boulevard | shared-use trail | |

TYPICAL 66' RIGHT-OF-WAY



RECEIVED JUN 2 4 2016
city of colden

June 22, 2016

James N. Grube, P.E.
Director of Transportation and County Engineer
Transportation Department
1600 Prairie Drive
Medina, Minnesota 55340

7800 Golden Valley Road Golden Valley, MN 55427

Re:

Letter of Support for Hennepin County's Regional Solicitation Application and Project CSAH 66 (Golden Valley Road) Reconstruction and Trail Implementation Regent Avenue to Bonnie Lane

Dear Mr. Grube:

The City of Golden Valley supports Hennepin County's federal funding application through the Regional Solicitation for the proposed CSAH 66 (Golden Valley Road) roadway reconstruction and regional trail project from Regent Avenue to Bonnie Lane, which will include the following improvements:

- Full roadway reconstruction
- Traffic signal replacement/upgrades
- Sidewalk replacement and implementation
- Regional trail implementation
- Streetscaping and greening elements

The city supports this county reconstruction project, as it will improve capacity, access, and safety for multiple transportation modes. Improvements along this corridor will enhance the livability and quality of life for Golden Valley and Hennepin County residents.

Thank you for making us aware of this application effort and the opportunity to provide support. The city looks forward to working with you on this project.

Sincerely,

Marc Nevinski

Physical Development Director

Cc: Shep Harris, Mayor

Timothy J. Cruikshank, City Manager

Jeff Oliver, PE, City Engineer



Three Rivers
Park District
Board of
Commissioners

June 9, 2016

Penny Steele District 1 James N. Grube, P.E.
Director of Transportation and County Engineer
Transportation Department

1600 Prairie Drive

Medina, Minnesota 55340

Jennifer DeJournett District 2 Re: Letter of Support for Regional Solicitation Application CSAH 66 (Golden Valley Road) Reconstruction and Trail Implementation Regent Avenue to Bonnie Lane

Dear Mr. Grube:

Daniel Freeman, Vice Chair District 3 Three Rivers Park District supports Hennepin County's federal funding application through the Regional Solicitation for the proposed CSAH 66 (Golden Valley Road) roadway reconstruction and regional trail project from Regent Avenue to Bonnie Lane, which will include the following improvements:

John Gunyou, Chair District 4

- Full roadway reconstruction
- Implementation of the Bassett Creek Regional Trail in the project area
- Sidewalk replacement and streetscaping improvements
- Traffic signal replacement/upgrades
- Pedestrian and bicycle crossing improvements

John Gibbs District 5 Three Rivers Park District supports this project as it fills one of the last missing critical gaps of the Bassett Creek Regional Trail. The Bassett Creek Regional Trail is a multi-use off-road trail which provides a high level of safety and comfort to people biking and walking. This facility type serves people which fall into one of the three following bicycle attitude and perception categories: strong and fearless, enthusiastic and confident, and interested but concerned – totally over 60 percent of the population.

Gene Kay Appointed At Large

Improvements along this corridor will enhance the livability and quality of life for Golden Valley and Hennepin County residents, and improved connectivity and mobility options for users of Three Rivers Park District's trail system. Three Rivers Park District looks forward to working with you on this project.


Steve Antolak Appointed At Large

Sincerely,


Boe Carlson, Superintendent Three Rivers Park District

Boe Carlson Superintendent

G:\Planning\Administration\Letters of Support\Hennepin County - GV Road 2016 Fed App.docx



# **APPENDIX A**



Segment	From	Ta	Along   Through	Length
Golden Valle	y			
G	Highway 100 Pedestrian Bridge	Theodore Wirth Parkway (Theodore Wirth Regional Park)	Unity Avenue   Open Space   Toledo Avenue   Open Space   Scott Avenue   Regent Avenue   Golden Vailey Road/CR66	
G1	Highway 100 Pedestrian Bridge	Minnaqua Drive	Unity Avenue (east side)   Open Space	0.34
G2	Minnaqua Drive	Regent Avenue	Toledo Avenue (east side)   Open Space   Scott Avenue (east side)	0.31
G3	Westbend Road	Golden Valley Road/CR 66	Regent Avenue (west side)	0,18
G4	Regent Avenue	Theodore Wirth Parkway (Theodore Wirth Regional Park)	Golden Valley Road/CR 66 (south side)	1,15
	ž.		Subtotal	1.98 miles


Segment G - Golden Valley

Source: Three Rivers Park District



Appendix C: Sections 2 & 3 Alignment

Figure 7.8: Existing and Proposed Trails and Sidewalks




Date: July 30, 2009

Sources: SEH for proposed trail layer, MnDOT for neighboring city streets, Hennepin County Surveyors Office for Property Lines (2006), City of Golden Valley for all other layers

**Figure 3.9: Pedestrian Circulation Enhancements** 

This map shows recommended pedestrian circulation enhancement to better support station area livability and LRT station access.





**Figure 3.10: Bicycle Circulation Enhancements** 

This map shows recommended bicycle circulation enhancement to better support station area livability and LRT station access.






Figure 3.17: Public Realm Improvements

This map depicts public realm improvements that provide economic, environmental and social benefits that are supportive of station area livability.

Enhanced Streetscape
Trail Lighting / Roadway Lighting
Park
Wayfinding
A Public Art
Vertical Circulation
Redevelopment Opportunity Site
Planned LRT Station
Bottineau LRT Alignment
LRT Station Half Mile Buffer
Railroad
Proposed Sidewalks
Existing Sidewalks


Proposed Paved Trail


Proposed On-Street Bike

Existing On-Street Bike

Facility

**Existing Paved Trail** 





Site: 03

TOTAL VOLUME DATA CSAH 66 (GOLDEN VALLY RD.) E. OF -T.H. 100 / STUDY # 4057

Weekly Volume, per Channel

E.B.												
	Mon	Tue	Wed	Thu	Fri	Sat	Sun	Mon - Fri	Weekly			
Interval Start	5/16/2016	5/17/2016	5/18/2016	5/19/2016	5/20/2016	5/21/2016	5/22/2016	Average	Average			
12:00 AM	-	-	61	53	-	-	-	57.0	57.0			
1:00 AM	-	-	33	35	-	-	-	34.0	34.0			
2:00 AM	-	-	31	34	-	-	-	32.5	32.5			
3:00 AM	-	-	17	13	-	-	-	15.0	15.0			
4:00 AM	-	-	20	20	-	-	-	20.0	20.0			
5:00 AM	-	-	43	45	-	-	-	44.0	44.0			
6:00 AM	-	-	272	270	-	-	-	271.0	271.0			
7:00 AM	-	-	445	425	-	-	-	435.0	435.0			
8:00 AM	-	-	559	502	-	-	-	530.5	530.5			
9:00 AM	-	-	480	483	-	-	-	481.5	481.5			
10:00 AM	-	-	376	418	-	-	-	397.0	397.0			
11:00 AM	-	464	441	-	-	-	-	452.5	452.5			
12:00 PM	-	525	551	-	-	-	-	538.0	538.0			
1:00 PM	-	538	506	-	-	-	-	522.0	522.0			
2:00 PM	-	616	626	-	-	-	-	621.0	621.0			
3:00 PM	-	712	762	-	-	-	-	737.0	737.0			
4:00 PM	-	913	882	-	-	-	-	897.5	897.5			
5:00 PM	-	944	1007	-	-	-	-	975.5	975.5			
6:00 PM	-	819	800	-	-	-	-	809.5	809.5			
7:00 PM	-	570	553	-	-	-	-	561.5	561.5			
8:00 PM	-	553	503	-	-	-	-	528.0	528.0			
9:00 PM	-	384	413	-	-	-	-	398.5	398.5			
10:00 PM	-	220	231	-	-	-	-	225.5	225.5			
11:00 PM	-	108	116	-	-	-	-	112.0	112.0			
Totals	0	7366	9728	2298	0	0	0	9696.0	9696.0			
				<u>Peak</u> H	<u>lours</u>							
12:00 AM - 12:00 PM	-	11:00 AM	8:00 AM	8:00 AM	-	-	-	8:00 AM	8:00 AM			
Volume	-	464	559	502	-	-	-	530.5	530.5			
12:00 PM - 12:00 AM	-	5:00 PM	5:00 PM	-	-	-	-	5:00 PM	5:00 PM			
Volume	-	944	1007	-	-	-	-	975.5	975.5			

EB volume: 9,696
WB volume: 9,126.5
Total volume: 18,822.5

Adjustment factor: 1.142

2016 AADT: 16,500

03-70-5-17-16-V.rdf Report Date: 5/20/2016 9:04 AM 1

Site: 03

TOTAL VOLUME DATA CSAH 66 (GOLDEN VALLY RD.) E. OF -T.H. 100 / STDY 4057

Weekly Volume, per Channel

WB. Mon Tue Wed Thu Fri Sat Sun Mon - Fri Weekly 5/20/2016 Average 5/17/2016 5/18/2016 5/19/2016 5/21/2016 5/22/2016 Interval Start 5/16/2016 Average 12:00 AM 40 40.0 40 40.0 1:00 AM 19 13 16.0 16.0 2:00 AM 12 11 11.5 11.5 3:00 AM 16 14 15.0 15.0 4:00 AM 78 70 74.0 74.0 5:00 AM 193 190 191.5 191.5 6:00 AM 532 497 514.5 514.5 7:00 AM 849 868 858.5 858.5 669 648.0 648.0 8:00 AM \_ 627 594 9:00 AM 587 590.5 590.5 10:00 AM 449 495 472.0 472.0 493 479.0 479.0 11:00 AM 465 493 504.5 12:00 PM 516 504.5 1:00 PM 483 535 509.0 509.0 2:00 PM 562 549 555.5 555.5 3:00 PM 632 661 646.5 646.5 4:00 PM 659 634 646.5 646.5 595 5:00 PM 655 625.0 625.0 6:00 PM 556 594 575.0 575.0 409.5 7:00 PM 400 419 409.5 8:00 PM 338.5 338.5 361 316 \_ \_ \_ \_ 9:00 PM 239 213.0 213.0 187 10:00 PM 130 122.5 \_ 115 \_ \_ 122.5 11:00 PM -68 73 70.5 70.5 Totals 5604 9188 0 9126.5 0 3461 0 0 9126.5 **Peak Hours** 12:00 AM -11:00 AM 7:00 AM 7:00 AM 7:00 AM 7:00 AM 12:00 PM 493 849 868 858.5 858.5 Volume 12:00 PM -4:00 PM 3:00 PM 3:00 PM 3:00 PM 12:00 AM 659 661 646.5 646.5 Volume

03-71-5-17-16-V.rdf Report Date: 5/20/2016 9:24 AM 1

VEHICLE CLASSIFICATION DATA CSAH 66 (GOLDEN VALLY RD.) E. OF-T.H. 100 / STUDY # 4042

11:00 PM

Daily Average

112.0

9696.0

0.0

39.5

102.0

8232.5

9.0

991.5

1.0

119.5

0.0

204.0

Site: 03 Tuesday, 5/17/2016 11:00 AM -Thursday, 5/19/2016 11:00 AM

# Classification Grand Totals Hourly Averages

### E.B. 2 Axle 6 3 Axle 4 Axle 5 Axle >6 Axle <6 Axle 6 Axle >6 Axle Motor Cars & 2 Axle <5 Axle Tailgating Total Buses Double Double Multi Multi **Bikes** Trailers Long Tire Single Single Double Multi Interval Start 12:00 AM 57.0 0.0 55.0 1.5 0.0 0.5 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 1:00 AM 34.0 0.0 29.0 5.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 2:00 AM 32.5 0.0 28.0 4.5 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 3:00 AM 15.0 0.0 14.0 0.5 0.0 0.0 0.5 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 4:00 AM 20.0 0.0 16.0 2.0 1.0 0.0 0.5 0.0 0.5 0.0 0.0 0.0 0.0 0.0 0.0 5:00 AM 44.0 0.0 35.5 6.5 1.0 1.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 7.0 6:00 AM 271.0 1.5 233.0 21.5 6.0 0.5 0.0 1.5 0.0 0.0 0.0 0.0 0.0 0.0 7:00 AM 435.0 2.0 361.5 46.5 8.5 11.5 0.5 0.0 3.5 0.5 0.0 0.5 0.0 0.0 0.0 8:00 AM 530.5 1.5 426.5 66.0 7.0 20.5 1.0 0.0 5.5 1.5 0.0 1.0 0.0 0.0 0.0 9:00 AM 66.0 7.0 18.5 1.0 0.0 3.5 0.5 0.0 2.0 0.0 0.0 0.5 481.5 1.0 381.5 10:00 AM 397.0 1.0 306.5 61.0 5.5 17.5 1.5 0.0 2.5 0.5 0.0 1.0 0.0 0.0 0.0 11:00 AM 2.5 0.5 0.0 452.5 2.0 375.5 51.0 18.0 2.0 0.0 0.0 1.0 0.0 0.0 0.0 12:00 PM 538.0 3.0 435.0 65.5 7.5 19.0 1.5 0.0 5.5 0.0 0.0 1.0 0.0 0.0 0.0 1:00 PM 522.0 1.5 436.0 65.5 3.0 11.5 0.0 0.0 3.5 0.0 0.0 1.0 0.0 0.0 0.0 2:00 PM 621.0 2.5 505.5 75.0 13.5 15.5 1.5 0.0 7.5 0.0 0.0 0.0 0.0 0.0 0.0 3:00 PM 737.0 612.0 75.5 19.0 19.0 0.5 0.0 5.5 0.0 0.0 1.0 0.0 0.0 0.5 4.0 4:00 PM 897.5 3.0 767.0 82.5 16.5 14.0 0.5 0.0 10.5 0.0 0.0 2.5 0.0 1.0 0.0 5:00 PM 975.5 5.0 842.0 92.0 9.0 11.0 0.0 1.0 12.5 0.0 0.0 2.0 0.0 0.5 0.5 6:00 PM 809.5 4.0 723.5 64.5 5.0 6.0 0.0 0.0 6.0 0.0 0.0 0.0 0.0 0.0 0.5 7:00 PM 561.5 3.0 499.0 51.5 1.0 3.5 0.0 0.0 3.5 0.0 0.0 0.0 0.0 0.0 0.0 8:00 PM 528.0 2.0 480.0 34.5 2.5 5.5 0.0 0.0 3.0 0.0 0.0 0.5 0.0 0.0 0.0 9:00 PM 398.5 2.5 363.5 27.5 2.0 2.5 0.0 0.0 0.5 0.0 0.0 0.0 0.0 0.0 0.0 10:00 PM 225.5 0.0 205.0 16.5 1.0 2.0 0.0 0.0 1.0 0.0 0.0 0.0 0.0 0.0 0.0

Study Grand Totals															
	Total	Motor Bikes	Cars & Trailers	2 Axle Long	Buses	2 Axle 6 Tire	3 Axle Single	4 Axle Single	<5 Axle Double	5 Axle Double	>6 Axle Double	<6 Axle Multi	6 Axle Multi	>6 Axle Multi	Tailgating
 E.B.	19392	79	16465	1983	239	408	20	2	156	6	0	27	0	3	4
		0.4 %	84.9 %	10.2 %	1.2 %	2.1 %	0.1 %	0.0 %	0.8 %	0.0 %	0.0 %	0.1 %	0.0 %	0.0 %	0.0 %

0.0

10.0

0.0

1.0

0.0

78.0

0.0

3.0

0.0

0.0

0.0

13.5

0.0

0.0

0.0

1.5

0.0

2.0

03-70-5-17-16-C.rdf Report Date: 5/20/2016 8:58 AM

VEHICLE CLASSIFICATION DATA CSAH 66 (GOLDEN VALLY RD.) E. OF -T.H. 100 / STUDY # 4042

Daily Average

9126.5

58.0

7351.5

Site: 03 Tuesday, 5/17/2016 11:00 AM -Thursday, 5/19/2016 11:00 AM

### Classification Grand Totals

### **Hourly Averages** W.B. 3 Axle 4 Axle Motor Cars & 2 Axle 2 Axle 6 <5 Axle 5 Axle >6 Axle <6 Axle 6 Axle >6 Axle Total Buses Tailgating Double Double Multi **Bikes** Trailers Long Tire Single Single Double Multi Multi Interval Start 12:00 AM 40.0 0.5 38.5 1.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 1:00 AM 16.0 0.0 14.5 1.5 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 2:00 AM 11.5 0.0 9.5 2.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 3:00 AM 15.0 0.0 11.5 3.5 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 4:00 AM 74.0 0.0 67.0 6.0 1.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 5:00 AM 191.5 0.0 157.5 27.5 1.5 4.5 0.0 0.0 0.5 0.0 0.0 0.0 0.0 0.0 0.0 6:00 AM 2.5 514.5 1.5 432.5 60.5 6.5 9.5 1.0 0.0 0.0 0.0 0.5 0.0 0.0 0.0 7:00 AM 858.5 9.0 669.5 106.5 24.0 17.5 1.0 0.0 26.0 0.0 0.0 3.5 0.0 1.0 0.5 8:00 AM 648.0 2.5 534.5 72.5 10.5 16.5 0.5 0.0 10.0 0.5 0.0 0.5 0.0 0.0 0.0 9:00 AM 12.5 18.0 0.5 0.0 7.0 1.0 0.0 1.5 0.0 0.5 590.5 4.0 454.5 91.0 0.0 10:00 AM 472.0 1.5 367.5 70.5 6.5 18.0 1.0 0.5 4.5 0.5 0.0 1.5 0.0 0.0 0.0 11:00 AM 22.0 0.5 0.5 0.5 479.0 1.5 363.5 80.0 3.5 6.0 0.0 0.0 0.0 0.0 1.0 12:00 PM 504.5 2.0 396.5 77.5 3.0 17.5 1.0 0.0 5.0 0.5 0.0 1.0 0.0 0.0 0.5 1:00 PM 509.0 1.0 402.0 83.0 3.0 16.5 0.0 0.0 3.0 0.0 0.0 0.5 0.0 0.0 0.0 2:00 PM 555.5 22.5 0.5 0.0 8.5 0.0 0.0 0.5 0.5 4.5 421.5 91.0 6.0 0.0 0.0 3:00 PM 646.5 2.0 493.5 98.5 15.0 19.0 1.0 0.0 15.0 0.0 0.0 1.5 0.5 0.0 0.5 4:00 PM 646.5 523.5 80.0 11.5 12.0 0.5 0.0 11.5 0.0 0.0 1.0 0.0 0.0 0.5 6.0 5:00 PM 625.0 6.0 517.0 73.0 7.0 10.5 1.0 0.0 8.5 0.5 0.0 1.0 0.0 0.0 0.5 6:00 PM 575.0 6.5 474.0 71.0 4.0 11.0 0.0 0.0 7.5 0.5 0.0 0.5 0.0 0.0 0.0 7:00 PM 409.5 3.5 355.5 0.0 2.5 0.0 0.0 2.0 0.0 0.0 0.5 0.0 0.0 0.0 45.5 8:00 PM 338.5 4.0 285.0 39.0 2.5 6.5 0.0 0.0 0.5 0.0 0.0 1.0 0.0 0.0 0.0 9:00 PM 213.0 1.5 189.5 20.0 1.0 1.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 10:00 PM 122.5 0.0 109.5 10.0 1.5 0.5 0.0 0.0 1.0 0.0 0.0 0.0 0.0 0.0 0.0 11:00 PM 70.5 0.5 63.5 5.5 1.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0

						Sti	iay Grana i	otais							
	Total	Motor Bikes	Cars & Trailers	2 Axle Long	Buses	2 Axle 6 Tire	3 Axle Single	4 Axle Single	<5 Axle Double	5 Axle Double	>6 Axle Double	<6 Axle Multi	6 Axle Multi	>6 Axle Multi	Tailgating
W.B	. 18253	116	14703	2433	243	451	17	2	238	8	0	30	1	2	9
		0.6 %	80.6 %	13.3 %	1.3 %	2.5 %	0.1 %	0.0 %	1.3 %	0.0 %	0.0 %	0.2 %	0.0 %	0.0 %	0.0 %

8.5

Charles Comment Take In

1.0

119.0

4.0

0.0

15.0

0.5

1.0

4.5

EB ONLY - SUM OF DAILY AVG CLASSES 4 THROUGH 13 = 430.5 WB ONLY - SUM OF DAILY AVG CLASSES 4 THROUGH 13 = 496

1216.5

121.5

225.5

DAILY TOTAL HEAVY COMMERCIAL VEHICLES = 926.5

03-71-5-17-16-C.rdf Report Date: 5/20/2016 9:14 AM

From: <u>Filipi, Mark</u>
To: <u>Sierra Saunders</u>

Cc: <u>Jason R Pieper; Jason D Gottfried; Carla J Stueve; Robert H. Byers</u>

Subject: RE: 2016 Regional Solicitation - Forecast AADT"s

**Date:** Thursday, June 16, 2016 10:23:49 AM

image006.png image008.png image010.png

Sierra,

Attachments:

Here is the data you requested. It is generated from the model runs from the most recent update of the Council's 2040 Transportation Policy Plan and is based in the four-step trip-based regional travel demand forecast model.

Project Forecast Volume

CSAH 15 (Shoreline Dr) Bridge Replacement 20,900
CSAH 19 (Manitou Rd/Shadywood Rd) Bridge Rehabilitation 16,200
CSAH 23 (Marshall St NE) 10,500

CSAH 32 (Penn Ave) Reconstruction 16,200 (Note: The 2014 AADT

you cite of 12,800 is actually outside

your project area. 10,800 is

the only AADT reported in your

project area)

CSAH 66 (Golden Valley Rd) Reconstruction 19,900 (West of Noble Ave.)

10,200 (East of Indiana Ave.)

CSAH 81 (Bottineau Blvd) Expansion 51,100 CSAH 81 (Broadway Ave) Bridge Replacement 24,700

CSAH 152 (Webber Pkwy) Reconstruction

This re

This roadway is not in the regional model.

The model links in the area show an annualized

armaanzea

growth rate of 0.5%. When applied

to the 13,700

2013 volume, this grows to 16,100.

If you have any questions, please feel free to contact me.



### Mark Filipi, AICP PTP

Manager, Technical Planning Support
Metropolitan Transportation Services
mark.filipi@metc.state.mn.us
P.651.602.1725 | F.651.602.1739
390 North Robert Street | St. Paul, MN | 55101 | metrocouncil.org









**From:** Sierra Saunders [mailto:Sierra.Saunders@hennepin.us]

**Sent:** Wednesday, June 15, 2016 8:02 AM

**To:** Filipi, Mark < Mark. Filipi@metc.state.mn.us>

**Cc:** Jason R Pieper <Jason.Pieper@hennepin.us>; Jason Gottfried <Jason.gottfried@hennepin.us>; Carla Stueve <Carla.Stueve@hennepin.us>; Robert H. Byers <Robert.Byers@hennepin.us>

**Subject:** 2016 Regional Solicitation - Forecast AADT's

Greetings Mark,

I'm writing to request 2040 Forecast AADT information for the Regional Solicitation. Below is the list of projects with our most recent adjusted traffic counts. Project location maps are attached, in the same order as the list below:

- CSAH 15 (Shoreline Dr) Bridge Replacement (Over Browns Bay/Tanager Channel): 16,500
   (2014 AADT)
- CSAH 19 (Manitou Rd/Shadywood Rd) Bridge Rehabilitation (Over Narrows Channel): 11,900
   (2016 AADT)
- CSAH 23 (Marshall St NE) Reconstruction: **8,800** (2016 AADT)
- CSAH 32 (Penn Ave) Reconstruction: **12,800** (2014 AADT)
- CSAH 66 (Golden Valley Rd) Reconstruction: **11,900** (2016 AADT)
- CSAH 81 (Bottineau Blvd) Expansion (4-lane divided to 6-lane divided): **21,400** (2013 AADT)
- CSAH 81 (Broadway Ave) Bridge Replacement (Over CSAH 153 [Lowry Ave]): 12,100 (2016 AADT)
- CSAH 152 (Webber Pkwy) Reconstruction: **13,700** (2013 AADT)

Please let me know if you need any additional information, and thank you!

Sierra Saunders Multimodal Planner Hennepin County Public Works 1600 Prairie Drive, Medina, MN 55340

Office: 612.596.0364

sierra.saunders@hennepin.us

**Disclaimer:** If you are not the intended recipient of this message, please immediately notify the sender of the transmission error and then promptly delete this message from your computer system.

# **Hennepin County**

Department of Public Works
Transportation Planning Division
Traffic Movement Study

Turning Movement Study CSAH 066 & Regent Ave Thursday, June 16th, 2016 7 AM - 9 AM & 4 PM - 6 PM File Name: STDY 4071

Site Code: 4071

Start Date : 6/16/2016

Page No : 1

Groups	Printed-	Cars -	Hvy	Comm
--------	----------	--------	-----	------

									•	ted- Cai	S - HV										1
		Re	egent A	ve			C	SAH 0	66			Re	egent A	ve			C	SAH 0	66		
		So	uthbou	nd			W	estbou	nd			No	rthbou	und			E	astbou	nd		
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
07:00 AM	13	3	3	0	19	1	70	1	0	72	1	0	5	0	6	2	73	0	3	78	175
07:15 AM	14	3	3	2	22	0	86	1	0	87	0	1	8	2	11	5	91	4	0	100	220
07:30 AM	19	5	6	2	32	0	105	5	0	110	2	0	7	1	10	6	104	8	0	118	270
07:45 AM	20	6	3	0	29	1	105	3	0	109	0	1	9	1	11	7	128	4	0	139	288
Total	66	17	15	4	102	2	366	10	0	378	3	2	29	4	38	20	396	16	3	435	953
08:00 AM	30	3	4	1	38	3	78	0	0	81	0	1	11	0	12	11	100	7	2	120	251
08:15 AM	21	2	0	2	25	3	103	2	0	108	0	0	10	0	10	5	99	5	0	109	252
08:30 AM	18	7	2	0	27	1	84	3	0	88	1	2	7	0	10	6	118	10	1	135	260
08:45 AM	11	3	1	0	15	0	87	1	0	88	2	1	9	1	13	8	104	13	0	125	241
Total	80	15	7	3	105	7	352	6	0	365	3	4	37	1	45	30	421	35	3	489	1004
****BREAK																					
04:00 PM	7	1	1	0	9	0	108	2	0	110	2	1	2	1	6	13	173	13	1	200	325
04:15 PM	13	0	0	0	13	2	103	2	0	107	4	5	5	0	14	15	176	21	0	212	346
04:30 PM	13	3	2	0	18	2	103	0	1	106	0	1	7	1	9	15	207	32	2	256	389
04:45 PM	10	2	0	0	12	4	117	2	0	123	3	2	2	4	11	12	176	30	4	222	368
Total	43	6	3	0	52	8	431	6	1	446	9	9	16	6	40	55	732	96	7	890	1428
																					'
05:00 PM	22	0	2	1	25	3	107	5	1	116	6	7	5	2	20	13	203	24	3	243	404
05:15 PM	14	3	3	1	21	1	97	3	0	101	7	6	13	0	26	11	219	27	0	257	405
05:30 PM	13	1	1	0	15	1	119	3	0	123	1	2	8	0	11	16	189	24	3	232	381
05:45 PM	13	1	1	0	15	1	96	2	0	99	3	1	2	2	8	18	200	27	3	248	370
Total	62	5	7	2	76	6	419	13	1	439	17	16	28	4	65	58	811	102	9	980	1560
Grand Total	251	43	32	9	335	23	1568	35	2	1628	32	31	110	15	188	163	2360	249	22	2794	4945
Apprch %	74.9	12.8	9.6	2.7		1.4	96.3	2.1	0.1		17	16.5	58.5	8		5.8	84.5	8.9	0.8		
Total %	5.1	0.9	0.6	0.2	6.8	0.5	31.7	0.7	0	32.9	0.6	0.6	2.2	0.3	3.8	3.3	47.7	5	0.4	56.5	
Cars	248	43	31	2	324	22	1538	32	0	1592	29	30	108	2	169	160	2311	247	12	2730	4815
% Cars	98.8	100	96.9	22.2	96.7	95.7	98.1	91.4	0	97.8	90.6	96.8	98.2	13.3	89.9	98.2	97.9	99.2	54.5	97.7	97.4
Hvy Comm	3	0	1	7	11	1	30	3	2	36	3	1	2	13	19	3	49	2	10	64	130
% Hvy Comm	1.2	0	3.1	77.8	3.3	4.3	1.9	8.6	100	2.2	9.4	3.2	1.8	86.7	10.1	1.8	2.1	0.8	45.5	2.3	2.6
comm		9	2.1	, ,	0.0	5		0.0	-00		, ,	٥.2	1.5	00.,	10.1	1.0		0.0		5	

# **Hennepin County**

Department of Public Works
Transportation Planning Division
Traffic Movement Study


Turning Movement Study CSAH 066 & Regent Ave Thursday, June 16th, 2016 7 AM - 9 AM & 4 PM - 6 PM File Name: STDY 4071

Site Code: 4071

Start Date : 6/16/2016

Page No : 4

			egent A				_	SAH 0					egent A					CSAH ( astbou			
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Ana	alysis F	rom 07:	:00 AM	to 11:4	45 AM - 1	Peak 1 o	of 1														
Peak Hour for	Entire I	ntersec	tion Be	gins at	07:30 AN	Л															
07:30 AM	19	5	6	2	32	0	105	5	0	110	2	0	7	1	10	6	104	8	0	118	270
07:45 AM	20	6	3	0	29	1	105	3	0	109	0	1	9	1	11	7	128	4	0	139	288
08:00 AM	30	3	4	1	38	3	78	0	0	81	0	1	11	0	12	11	100	7	2	120	251
08:15 AM	21	2	0	2	25	3	103	2	0	108	0	0	10	0	10	5	99	5	0	109	252
Total Volume	90	16	13	5	124	7	391	10	0	408	2	2	37	2	43	29	431	24	2	486	1061
% App. Total	72.6	12.9	10.5	4		1.7	95.8	2.5	0		4.7	4.7	86	4.7		6	88.7	4.9	0.4		
PHF	.750	.667	.542	.625	.816	.583	.931	.500	.000	.927	.250	.500	.841	.500	.896	.659	.842	.750	.250	.874	.921



# **Hennepin County**

Department of Public Works
Transportation Planning Division
Traffic Movement Study


Turning Movement Study CSAH 066 & Regent Ave Thursday, June 16th, 2016 7 AM - 9 AM & 4 PM - 6 PM File Name: STDY 4071

Site Code: 4071

Start Date : 6/16/2016

Page No : 6

			egent A				_	SAH 0					egent A					SAH 0			
Start Time	Right Thru Left Peds App					Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour An								Lore	reas	App. Total	rugin	Tinu	Dert	1 cus	Арр. Тока	reigne	Tinu	Dert	Teas	App. Total	Inc. rotar
Peak Hour for	-																				
04:30 PM	13	3	2	0	18	2	103	0	1	106	0	1	7	1	9	15	207	32	2	256	389
04:45 PM	10	2	0	0	12	4	117	2	0	123	3	2	2	4	11	12	176	30	4	222	368
05:00 PM	22	0	2	1	25	3	107	5	1	116	6	7	5	2	20	13	203	24	3	243	404
05:15 PM	14	3	3	1	21	1	97	3	0	101	7	6	13	0	26	11	219	27	0	257	405
Total Volume	59	8	7	2	76	10	424	10	2	446	16	16	27	7	66	51	805	113	9	978	1566
% App. Total	77.6	10.5	9.2	2.6		2.2	95.1	2.2	0.4		24.2	24.2	40.9	10.6		5.2	82.3	11.6	0.9		
PHF	.670	.667	.583	.500	.760	.625	.906	.500	.500	.907	.571	.571	.519	.438	.635	.850	.919	.883	.563	.951	.967



CSAH 66 - All Crashes 2013-2015 Crash Data Provided by MnDOT TIS Office

SYS	NUM	REF_POINT	GIS_ROUTE	GIS_TM	RD_DIR	ELEM	RELY	INV	R_U	ATP	со	CITY	DOW	MONTH	DAY	YEAR	TIME	SEV	NUM_KILLED	NUM_VEH	JUNC	SL TYPE	DIAG	LOC1	TCD	LIT	WTHR1	WTHR2	SURF	CHAR	DESGN	ACC_NUM
04	27000066	000+00.830	0427000066	0.830	Z		1	3	U	UNITS 1 AND 2 WERE WB ON DULUTH ST. UNIT 2 ATTEMPTED TO STOP FOR THE STOP SIGN AT DULUTH/REGENT AND	27	1495	5-Thu	2	14	2013	0801	С	0	2	4	35 1	1	1	3	1	2	1	3	2	5	130450070
04	27000066	000+00.830	0427000066	0.830	W		1	3	U	UNIT 2 WAS STOPPED FOR INTERSECTION STOP SIGN. UNIT 1 WAS SLOWING TO STOP WHEN HE SLID ON ICE AND B	27	1495	5-Thu	12	5	2013	1557	N	0	3	4	35 1	1	1	3	1	1	0	5	6	5	133390302
04	27000066	000+00.830	0427000066	0.830	N		1	3	U	UNIT 1 TRAVELING NORTHBOUND REGENT AVE N JUST NORTH OF COUNTY ROAD 66 (DULUTH ST). UNIT 1 STRUCK U	27	1495	5-Thu	1	2	2014	0101	N	0	2	1	30 2	1	2	98	6	1	0	5	1	8	140020014
04	27000066	000+00.880	0427000066	0.880	Z		1	3	U	VEH 2 WAS WAITING FOR TRAFFIC TO TURN LEFT INTO HIS DRIVEWAY. VEH 1 REAR ENDED VEH 2. NO INJURIES R	27	1495	7-Sat	12	21	2013	1014	N	0	2	1	30 1	1	1	98	1	2	0	1	6	5	133550111
04	27000066	000+00.880	0427000066	0.880	W		1	3	U	UNIT 1 WAS TURNING LEFT OUT OF BYERLYS PARKING LOT. UNIT 2 WAS WB DULUTH ST. UNIT 1 DRIVER'S VISIO'	27	1495	2-Mon	12	22	2014	1733	N	0	2	2	35 1	3	1	98	4	5	0	2	1	5	143570037
04	27000066	000+00.930	0427000066	0.930	Z		1	3	U	UNIT 1 TURNING FROM NB QUAIL TO GO WB GOLDEN VALLEY RD. UNIT 2 EB GOLDEN VALLEY RD APPROACHING QUAI	27	1495	6-Fri	1	24	2014	2230	N	0	2	2	35 1	3	1	4	4	2	0	5	6	8	140260017
04	27000066	000+00.935	0427000066	0.935	Z		1	3	U	UNIT 1 EB CR 66 CROSSED OVER CENTERLINE & STRUCK UNIT 2 WHICH WAS WB CR 66 IN #2 LN. DRVR 1 STATED	27	1495	2-Mon	2	16	2015	0634	C	0	2	1	35 1	90	1	98	4	4	0	2	6	5	150480015
04	27000066	000+00.990	0427000066	0.990	Z		1	1	U	DV1 NB WASHINGTON AVE. DV1 ATTEMPTED TO TURN WB ONTO BROADWAY AVE. V1 THEN LOST CONTROL, IMPACTED	27	1495	7-Sat	8	23	2014	0346	N	0	1	4	30 26	90	1	1	4	1	0	1	1	90	142370268
04	27000066	001+00.010	0427000066	1.010	Z		1	3	U	LIGHT WAS RED AND DR#1 LOOKED LIKE SHE WAS REACHING FOR SOMETHING AND NOT PAYING ATTENTION. DR#1 U	27	1495	6-Fri	2	22	2013	1638	N	0	2	2	35 1	1	1	1	1	1	1	1	1	8	130590028
04	27000066	001+00.037	0427000066	1.037	Z		1	3	U	UNIT 1 WAS WB ON CR 66. UNIT 1 OBSERVED WITNESS VEHICLE MAKE RIGHT TURN ONTO EB CR 66 FROM ORDWAY S	27	1495	6-Fri	5	24	2013	0701	В	0	1	1	35 51	90	1	4	1	1	0	1	7	6	131500023
04	27000066	001+00.140	0427000066	1.140	Z		1	3	U	UNITS 1 AND 2 WERE WB GOLDEN VALLEY RD PASSING NOBLE AVE N IN THE LEFT LANE. THE RIGHT LANE WAS CON	27	1495	2-Mon	7	7	2014	1323	N	0	2	2	35 1	2	1	1	1	2	0	1	5	5	141880080
04	27000066	001+00.217	0427000066	1.217	Z		1	3	U	UNIT 1 WAS WEST BOUND ON GOLDEN VALLEY RD NEAR MAJOR CIR. UNIT 1 LOST CONTROL ON THE SNOWY STREET,	27	1495	4-Wed	12	4	2013	1311	N	0	1	1	35 35	7	4	98	1	4	2	3	6	8	133380302
04	27000066	001+00.228	0427000066	1.228	W		1	3	U	UNIT#1 STATES SHE WAS STOPPED IN TRAFFIC. UNIT#2 STATES THEY WERE MOVING AND UNIT#1 CAME TO AN ABRU	27	1495	3-Tue	3	12	2013	1724	С	0	2	1	35 1	1	1	98	1	2	0	1	4	8	130710125
04	27000066	001+00.230	0427000066	1.230	W		1	3	U	DRIVER OF UNIT #1 SHOT HIMSELF WHILE DRIVING WESTBOUND GOLDEN VALLEY RD CAUSING HIM TO RUN OFF THE	27	1495	2-Mon	11	2	2015	0023	N	0	1	1	35 35	7	1	98	4	2	1	1	6	8	153140032
04	27000066	001+00.371	0427000066	1.371	Z		1	3	U	VEHICLE TRAVELING AT HIGH RATE OF SPEED. DRIVER LOST CONTROL AND LEFT ROADWAY. DR DROVE UP ON A RET	27	1495	3-Tue	9	30	2014	2318	Α	0	1	1	35 30	90	1	98	4	2	0	1	5	8	142740024
04	27000066	001+00.487	0427000066	1.487	E		1	3	U	UNIT 2 STARTED ON GREEN THEN SLOWED FOR EMERGENCY VEHICLES APPROACHING FROM BEHIND. UNIT 1 SAW EMER	27	1495	7-Sat	2	1	2014	1507	N	0	2	7	35 1	1	1	1	1	2	0	3	5	8	140320153
04	27000066	001+00.550	0427000066	1.550	Z		1	3	U	VEH #1 WAS TRAVELLING EB ON DULUTH ST. DR #2 WAS EXITING THE BYERLYS LOT. DR #2 DID NOT SEE VEH '	27	1495	5-Thu	7	25	2013	1311	N	0	2	2	35 1	6	1	4	1	2	0	1	1	5	132060155
04	27000066	001+00.550	0427000066	1.550	W		1	3	U	UNIT 2 STOPPED QUICKLY FOR VEHICLE IN FRONT OF IT THAT STOPPED QUICKLY FOR PEDESTRIAN CROSSING. UNI	27	1495	3-Tue	1	27	2015	1639	N	0	2	1	35 1	1	1	5	1	2	0	1	5	8	150270163
04	27000066	001+00.678	0427000066	1.678	W		1	3	U	UNIT#1 WB GOLDEN VALLEY ROAD SKIDS INTO OTHER LANE AND COLLIDES WITH UNIT#2. LIGHT SNOW/SLUSH ON RO	27	1495	3-Tue	3	5	2013	1118	В	0	2	1	35 1	9	1	98	1	4	90	4	5	8	130640151

Crashes identified in red occurred outside of the project area, and were not included in the benefit / cost calculation.

### CSAH 66 at Regent Avenue - Intersection

2013-	2015 Crash Dat	ta Provided by Mn	DOT TIS Office																											
SY	S NUM	REF_POINT	GIS_ROUTE	GIS_TM	RD_DIR	ELEM	RELY	INV	R_U	АТР	со	CITY	DOW	MONTH	DAY	YEAR TIN	IE SEV	NUM_KILLED NUM_VEH	JU	NC SL TYP	E DIA	G LOC	1 TCD	LIT	WTHR1	WTHR2	SURF	CHAR	DESGN	ACC_NUM
04	27000066	000+00.830	0427000066	0.83	3 Z		1	. 3	U	UNITS 1 AND 2 WERE WB ON DULUTH ST. UNIT 2 ATTEMPTED TO STOP FOR THE STOP SIGN AT DULUTH/REGENT AND	T	27 1495	5-Thu	2	14	2013 0801	С	0	2	4 35	1	1	1	3 1	2	1	3	2	5 1	.30450070
04	27000066	000+00.830	0427000066	0.83	3 W		1	. 3	U	UNIT 2 WAS STOPPED FOR INTERSECTION STOP SIGN. UNIT 1 WAS SLOWING TO STOP WHEN HE SLID ON ICE AND B	1	27 1495	5-Thu	12	5	2013 1557	N	0	3	4 35	1	1	1	3 1	1	. 0	5	6	5 1	.33390302
04	27000066	000+00.830	0427000066	0.83	3 N		1	. 3	U	UNIT 1 TRAVELING NORTHBOUND REGENT AVE N JUST NORTH OF COUNTY ROAD 66 (DULUTH ST). UNIT 1 STRUCK U		27 1495	5-Thu	1	2	2014 0101	N	0	2	1 30	2	1	2 9	8 6	1	0	5	1	8 1/	40020014

## CSAH 66 from Regent Ave to Noble Ave - Segment 2013-2015 Crash Data Provided by MnDOT TIS Office

SYS	NUM	REF POIN	NT GIS ROUTE	GIS TM	RD DIR	ELEM	RELY	INV	RU	R U	ATP	co	CITY	DOW	MONTH	DAY	YEAR	TIN	IE SEV	NUM KILLED	NUM VEH	JUNC	SL .	TYPE	DIAG LO	C1	TCD LI	T WT	HR1 WTHR2	SURF	CHAR	DESGN	ACC NUM
04	27000066	000+00.880	0427000066	0.88	Z			1	3 U		VEH 2 WAS WAITING FOR TRAFFIC TO TURN LEFT INTO HIS DRIVEWAY. VEH 1 REAR ENDED VEH 2. NO INJURIES R	27	1495	7-Sat	12		21 20	013 1014	N		) 2		30	1	1	1	98	1	2	)	1 6	5	5 133550111
04	27000066	000+00.930	0427000066	0.93	Z			1	3 U		UNIT 1 TURNING FROM NB QUAIL TO GO WB GOLDEN VALLEY RD. UNIT 2 EB GOLDEN VALLEY RD APPROACHING QUAI	27	1495	6-Fri	1		24 20	014 2230	N	(	) 2		35	1	3	1	4	4	2	)	5 6	5	8 140260017
04	27000066	000+00.935	0427000066	0.935	Z			1	3 U		UNIT 1 EB CR 66 CROSSED OVER CENTERLINE & STRUCK UNIT 2 WHICH WAS WB CR 66 IN #2 LN. DRVR 1 STATED	27	1495	2-Mon	2		16 20	015 0634	С	(	) 2		35	1	90	1	98	4	4	)	2 6	5	5 150480015
04	27000066	001+00.037	0427000066	1.037	Z			1	3 U		UNIT 1 WAS WB ON CR 66. UNIT 1 OBSERVED WITNESS VEHICLE MAKE RIGHT TURN ONTO EB CR 66 FROM ORDWAY S	27	1495	6-Fri	5		24 20	0701	В	(	1		35	51	90	1	4	1	1	)	1 7	7	6 131500023

### CSAH 66 at Noble Ave - Intersection 2013-2015 Crash Data Provided by MnDOT TIS Office

SYS         NUM         REF_POINT         GIS_ROUTE         GIS_TM         RD_DIR         ELEM         RELY         INV         R_U           04         27000066         001+00.140         0427000066         1.14 Z         1         3 U	АТР	co	CITY	DOW	MONTH	DAY	YEAR	TIME	SEV	NUM_KILLED 0	NUM_VEH	JUNC	SL TYP	PE DIAG	G LO	OC1 TCD	LIT	WTHR1	WTHR2	SURF	CHAR	DESGN	ACC_NUM
04 27000066 001+00.140 0427000066 1.14 Z 1 3 U	UNITS 1 AND 2 WERE WB GOLDEN VALLEY RD PASSING NOBLE AVE N IN THE LEFT LANE. THE RIGHT LANE WAS CON	27	1495	2-Mon	7	7	2014 1	1323	N	0		2 2	35	1	2	1	1 1		2 0	1	5	5 141	1880080

# CSAH 66 from Noble Ave to Bonnie Lane - Segment 2013-2015 Crash Data Provided by MnDOT TIS Office

		I TOVIGEG BY IVITID																											
SYS	NUM	REF_POINT	GIS_ROUTE	GIS_TM	RD_DIR	ELEM	RELY	INV	R_U	АТР	CO CITY	DOW	MONTH	DAY	YEAR TIME	SEV	NUM_KILLED	NUM_VEH	JUNC SI	. TYP	PE DIAG	LOC1	TCD	LIT	WTHR1	WTHR2	SURF	CHAR	DESGN ACC_NUM
04	27000066	001+00.217	0427000066	1.217 Z			1	3	U	UNIT 1 WAS WEST BOUND ON GOLDEN VALLEY RD NEAR MAJOR CIR. UNIT 1 LOST CONTROL ON THE SNOWY STREET,	27 1495	4-Wed	12	4	2013 1311	N	0	1	1	35	35	7	4 9	8 1	4	2	3	6	8 133380302
04	27000066	001+00.228	0427000066	1.228 W			1	3	U	UNIT#1 STATES SHE WAS STOPPED IN TRAFFIC. UNIT#2 STATES THEY WERE MOVING AND UNIT#1 CAME TO AN ABRU	27 1495	3-Tue	3	12	2013 1724	C	0	2	1	35	1	1	1 9	8 1	2	0	1	4	8 130710125
04	27000066	001+00.230	0427000066	1.23 W			1	3	U	DRIVER OF UNIT #1 SHOT HIMSELF WHILE DRIVING WESTBOUND GOLDEN VALLEY RD CAUSING HIM TO RUN OFF THE	27 1495	2-Mon	11	2	2015 0023	N	0	1	1	35	35	7	1 9	8 4	2	1	1	6	8 153140032
04	27000066	001+00.371	0427000066	1.371 Z			1	3	U	VEHICLE TRAVELING AT HIGH RATE OF SPEED. DRIVER LOST CONTROL AND LEFT ROADWAY. DR DROVE UP ON A RET	27 1495	3-Tue	9	30	2014 2318	Α	0	1	1	35	30	90	1 9	8 4	2	0	1	5	8 142740024
04	27000066	001+00.550	0427000066	1.55 W			1	3	U	UNIT 2 STOPPED QUICKLY FOR VEHICLE IN FRONT OF IT THAT STOPPED QUICKLY FOR PEDESTRIAN CROSSING. UNI	27 1495	3-Tue	1	27	2015 1639	N	0	2	1	35	1	1	1	5 1	2	0	1	5	8 150270163
04	27000066	001+00.678	0427000066	1.678 W			1	3	U	UNIT#1 WB GOLDEN VALLEY ROAD SKIDS INTO OTHER LANE AND COLLIDES WITH UNIT#2. LIGHT SNOW/SLUSH ON RO	27 1495	3-Tue	3	5	2013 1118	В	0	2	1	35	1	9	1 9	8 1	4	90	4	5	8 130640151

### CSAH 66 at Hidden Lakes Pkwy - Intersection

201:	.3-2015 Crash Data Provided by M	nDO1 115 Office																										
S	SYS NUM REF_POIN	T GIS_ROUTE	GIS_TM RD_DIR	ELEM RELY	INV	R_U	ATP	co	CITY	DOW	MONTH	DAY	YEAR	TIME	SEV	NUM_KILLED NUM_	VEH JUNC	SL	TYPE	DIAG	LOC1 TCD	LIT	WTHR1	WTHR2	SURF	CHAR	DESGN	ACC_NUM
04	27000066 001+00.010	0427000066	1.01 Z		1 3	U	LIGHT WAS RED AND DR#1 LOOKED LIKE SHE WAS REACHING FOR SOMETHING AND NOT PAYING ATTENTION. DR#1 U	27 149	95 6	i-Fri	2	22	2013	1638	N	0	2	2 35	1	1	1	1 1	1	1	1 1	1	8	130590028
04	27000066 001+00.487	0427000066	1.487 E		1 3	U	UNIT 2 STARTED ON GREEN THEN SLOWED FOR EMERGENCY VEHICLES APPROACHING FROM BEHIND. UNIT 1 SAW EMER	27 149	95 7	'-Sat	2	1	2014	1507	N	0	2	7 35	1	1	1	1 1	2	۲	3	5	8	140320153



**CMF ID: 194** 

### **Increased pavement friction**

**Description:** 

**Prior Condition: No Prior Condition(s)** 

**Category: Roadway** 

Study: Crash Reduction Factors for Traffic Engineering and ITS Improvements, Harkey et al., 2008

Crash Modification Factor (CMF)							
Value:	0.76						
Adjusted Standard Error:	0.03						
Unadjusted Standard Error:							

Crash Reduction Factor (CRF)							
Value:	24 (This value indicates a <b>decrease</b> in crashes)						
Adjusted Standard Error:	3						
Unadjusted Standard Error:							

	Applicability
Crash Type:	All
Crash Severity:	All
Roadway Types:	All
Number of Lanes:	
Road Division Type:	
Speed Limit:	

Агеа Туре:	All
Traffic Volume:	Minimum of All to Maximum of All
Time of Day:	
	If countermeasure is intersection-based
Intersection Type:	
Intersection Geometry:	
Traffic Control:	
Major Road Traffic Volume:	
Minor Road Traffic Volume:	
	Development Details
Date Range of Data Used:	
Municipality:	
State:	
Country:	
Type of Methodology Used:	Before/after using empirical Bayes or full Bayes
Sample Size Used:	
	Other Details
Included in Highway Safety Manual?	No
Date Added to Clearinghouse:	
Comments:	
[View the Full Study Details]	Export PDF  Export this detail page as a PDF file

For more information, contact **Karen Scurry**, FHWA Office of Safety Programs 609-637-4207



**CMF ID: 195** 

### **Increased pavement friction**

**Description:** 

**Prior Condition: No Prior Condition(s)** 

**Category: Roadway** 

Study: Crash Reduction Factors for Traffic Engineering and ITS Improvements, Harkey et al., 2008

Crash Modification Factor (CMF)							
Value:	0.43						
Adjusted Standard Error:	0.03						
Unadjusted Standard Error:							

Crash Reduction Factor (CRF)						
Value:	57 (This value indicates a <b>decrease</b> in crashes)					
Adjusted Standard Error:	3					
Unadjusted Standard Error:						

	Applicability
Crash Type:	Wet road
Crash Severity:	All
Roadway Types:	All
Number of Lanes:	
Road Division Type:	
Speed Limit:	

Area Type:	AII
Traffic Volume:	Minimum of All to Maximum of All
Time of Day:	
	If countermeasure is intersection-based
Intersection Type:	
Intersection Geometry:	
Traffic Control:	
Major Road Traffic Volume:	
Minor Road Traffic Volume:	
	Development Details
Date Range of Data Used:	
Municipality:	
State:	
Country:	
Type of Methodology Used:	Before/after using empirical Bayes or full Bayes
Sample Size Used:	
	Other Details
Included in Highway Safety Manual?	No
Date Added to Clearinghouse:	
Comments:	
[View the Full Study Details]	Export PDF  Export this detail page as a PDF file

For more information, contact **Karen Scurry**, FHWA Office of Safety Programs 609-637-4207



**CMF ID: 197** 

### **Increased pavement friction**

**Description:** 

**Prior Condition: No Prior Condition(s)** 

**Category: Roadway** 

Study: Crash Reduction Factors for Traffic Engineering and ITS Improvements, Harkey et al., 2008

Crash Modification Factor (CMF)							
Value:	0.58						
Adjusted Standard Error:	0.07						
Unadjusted Standard Error:							

Crash Reduction Factor (CRF)						
Value:	42 (This value indicates a <b>decrease</b> in crashes)					
Adjusted Standard Error:	7					
Unadjusted Standard Error:						

Applicability Applicability	
Crash Type:	Rear end
Crash Severity:	All
Roadway Types:	All
Number of Lanes:	
Road Division Type:	
Speed Limit:	

Area Type:	All
Traffic Volume:	Minimum of All to Maximum of All
Time of Day:	
	If countermeasure is intersection-based
Intersection Type:	
Intersection Geometry:	
Traffic Control:	
Major Road Traffic Volume:	
Minor Road Traffic Volume:	
	Development Details
Date Range of Data Used:	
Municipality:	
State:	
Country:	
Type of Methodology Used:	Before/after using empirical Bayes or full Bayes
Sample Size Used:	
	Other Details
Included in Highway Safety Manual?	No
Date Added to Clearinghouse:	
Comments:	
[View the Full Study Details]	Export PDF  Export this detail page as a PDF file

For more information, contact **Karen Scurry**, FHWA Office of Safety Programs 609-637-4207



**CMF ID: 198** 

### **Increased pavement friction**

**Description:** 

**Prior Condition: No Prior Condition(s)** 

**Category: Roadway** 

**Study:** Crash Reduction Factors for Traffic Engineering and ITS Improvements, Harkey et al., 2008

Star Quality Rating: \*\*\*\*\*\*\*\*

Crash Modification Factor (CMF)	
Value:	0.7
Adjusted Standard Error:	0.05
Unadjusted Standard Error:	

Crash Reduction Factor (CRF)	
Value:	30 (This value indicates a <b>decrease</b> in crashes)
Adjusted Standard Error:	5
Unadjusted Standard Error:	

Applicability	
Crash Type:	Single vehicle
Crash Severity:	All
Roadway Types:	All
Number of Lanes:	
Road Division Type:	
Speed Limit:	

Area Type:	All
Traffic Volume:	Minimum of All to Maximum of All
Time of Day:	
	If countermeasure is intersection-based
Intersection Type:	
Intersection Geometry:	
Traffic Control:	
Major Road Traffic Volume:	
Minor Road Traffic Volume:	
	Development Details
Date Range of Data Used:	
Municipality:	
State:	
Country:	
Type of Methodology Used:	Before/after using empirical Bayes or full Bayes
Sample Size Used:	
	Other Details
Included in Highway Safety Manual?	No
Date Added to Clearinghouse:	
Comments:	
[View the Full Study Details]	Export PDF  Export this detail page as a PDF file

For more information, contact **Karen Scurry**, FHWA Office of Safety Programs 609-637-4207



**CMF ID: 874** 

#### Narrow cross section (4 to 3 lanes with two way left-turn lane)

**Description:** 

Prior Condition: Four-lane cross-section, two in each direction.

**Category: Roadway** 

**Study:** The Safety and Operational Effects of Road Diet Conversion in Minnesota, Gates et al., 2007

Star Quality Rating: \*\*\*\*\* [View score details]

Crash Modification Factor (CMF)	
Value:	0.63
Adjusted Standard Error:	
Unadjusted Standard Error:	0.00632455532034

Crash Reduction Factor (CRF)	
Value:	37 (This value indicates a <b>decrease</b> in crashes)
Adjusted Standard Error:	
Unadjusted Standard Error:	0.632455532034

Applicability Applicability	
Crash Type:	All
Crash Severity:	All
Roadway Types:	Not specified
Number of Lanes:	4
Road Division Type:	Undivided
Speed Limit:	

Own Orealinghouse - Fown / Orkin Details
Urban
If countermeasure is intersection-based
Development Details
MN
Simple before/after
Crashes
516 Crashes
811 Crashes
Other Details

Other Details	
Included in Highway Safety Manual?	No
Date Added to Clearinghouse:	
Comments:	

[View the Full Study Details]

**Export PDF** 

Export this detail page as a PDF file

This site is funded by the U.S. Department of Transportation Federal Highway Administration and maintained by the University of North Carolina Highway Safety Research Center

For more information, contact **Karen Scurry**, FHWA Office of Safety Programs 609-637-4207



**CMF ID: 3072** 

# Change number of traffic signal cycles per hour on arterial with signal coordination from X to Y

**Description:** 

Prior Condition: No Prior Condition(s)

Category: Intersection traffic control

Study: Safety Effect of Arterial Signal Coordination, Wei and Tarko, 2011

#### **Crash Modification Factor (CMF)**

Value:  $100 * (1 - e^{-0.0444(Y-X)})$ 

**Adjusted Standard Error:** 

**Unadjusted Standard Error:** 

#### **Crash Reduction Factor (CRF)**

Value:  $e^{-0.0444(Y-X)}$ 

**Adjusted Standard Error:** 

**Unadjusted Standard Error:** 

Applicability	
Crash Type:	Rear end
Crash Severity:	All
Roadway Types:	All
Number of Lanes:	1 to 3

Road Division Type:	
Speed Limit:	30-50 mph
Area Type:	Urban and suburban
Traffic Volume:	
Time of Day:	All
If countermeasure is intersection-based	
Intersection Type:	Roadway/roadway (not interchange related)
Intersection Geometry:	
Traffic Control:	Signalized
Major Road Traffic Volume:	Maximum of 1840 veh/hr/ln Vehicles Per Hour
Minor Road Traffic Volume:	

Development Details	
Date Range of Data Used:	2003 to 2006
Municipality:	
State:	IN
Country:	USA
Type of Methodology Used:	Regression cross-section
Sample Size Used:	324 Crashes

Other Details	
Included in Highway Safety Manual?	No
Date Added to Clearinghouse:	
Comments:	

[View the Full Study Details]

**Export PDF** 

Export this detail page as a PDF file

This site is funded by the U.S. Department of Transportation Federal Highway Administration and maintained by the University of North Parolina Highway Safety Research Center

For more information, contact **Karen Scurry**, FHWA Office of Safety Programs 609-637-4207



**CMF ID: 194** 

### **Increased pavement friction**

**Description:** 

**Prior Condition: No Prior Condition(s)** 

**Category: Roadway** 

Study: Crash Reduction Factors for Traffic Engineering and ITS Improvements, Harkey et al., 2008

Crash Modification Factor (CMF)	
Value:	0.76
Adjusted Standard Error:	0.03
Unadjusted Standard Error:	

Crash Reduction Factor (CRF)	
Value:	24 (This value indicates a <b>decrease</b> in crashes)
Adjusted Standard Error:	3
Unadjusted Standard Error:	

Applicability	
Crash Type:	All
Crash Severity:	All
Roadway Types:	All
Number of Lanes:	
Road Division Type:	
Speed Limit:	

Агеа Туре:	All
Traffic Volume:	Minimum of All to Maximum of All
Time of Day:	
	If countermeasure is intersection-based
Intersection Type:	
Intersection Geometry:	
Traffic Control:	
Major Road Traffic Volume:	
Minor Road Traffic Volume:	
	Development Details
Date Range of Data Used:	
Municipality:	
State:	
Country:	
Type of Methodology Used:	Before/after using empirical Bayes or full Bayes
Sample Size Used:	
	Other Details
Included in Highway Safety Manual?	No
Date Added to Clearinghouse:	
Comments:	
[View the Full Study Details]	Export PDF  Export this detail page as a PDF file

For more information, contact **Karen Scurry**, FHWA Office of Safety Programs 609-637-4207



**CMF ID: 195** 

### **Increased pavement friction**

**Description:** 

**Prior Condition: No Prior Condition(s)** 

**Category: Roadway** 

Study: Crash Reduction Factors for Traffic Engineering and ITS Improvements, Harkey et al., 2008

Crash Modification Factor (CMF)	
Value:	0.43
Adjusted Standard Error:	0.03
Unadjusted Standard Error:	

Crash Reduction Factor (CRF)	
Value:	57 (This value indicates a <b>decrease</b> in crashes)
Adjusted Standard Error:	3
Unadjusted Standard Error:	

Applicability Applicability	
Crash Type:	Wet road
Crash Severity:	All
Roadway Types:	All
Number of Lanes:	
Road Division Type:	
Speed Limit:	

Area Type:	AII
Traffic Volume:	Minimum of All to Maximum of All
Time of Day:	
	If countermeasure is intersection-based
Intersection Type:	
Intersection Geometry:	
Traffic Control:	
Major Road Traffic Volume:	
Minor Road Traffic Volume:	
	Development Details
Date Range of Data Used:	
Municipality:	
State:	
Country:	
Type of Methodology Used:	Before/after using empirical Bayes or full Bayes
Sample Size Used:	
	Other Details
Included in Highway Safety Manual?	No
Date Added to Clearinghouse:	
Comments:	
[View the Full Study Details]	Export PDF  Export this detail page as a PDF file

For more information, contact **Karen Scurry**, FHWA Office of Safety Programs 609-637-4207



**CMF ID: 197** 

### **Increased pavement friction**

**Description:** 

**Prior Condition: No Prior Condition(s)** 

**Category: Roadway** 

Study: Crash Reduction Factors for Traffic Engineering and ITS Improvements, Harkey et al., 2008

Crash Modification Factor (CMF)	
Value:	0.58
Adjusted Standard Error:	0.07
Unadjusted Standard Error:	

Crash Reduction Factor (CRF)	
Value:	42 (This value indicates a <b>decrease</b> in crashes)
Adjusted Standard Error:	7
Unadjusted Standard Error:	

Applicability Applicability	
Crash Type:	Rear end
Crash Severity:	All
Roadway Types:	All
Number of Lanes:	
Road Division Type:	
Speed Limit:	

Area Type:	All
Traffic Volume:	Minimum of All to Maximum of All
Time of Day:	
	If countermeasure is intersection-based
Intersection Type:	
Intersection Geometry:	
Traffic Control:	
Major Road Traffic Volume:	
Minor Road Traffic Volume:	
	Development Details
Date Range of Data Used:	
Municipality:	
State:	
Country:	
Type of Methodology Used:	Before/after using empirical Bayes or full Bayes
Sample Size Used:	
	Other Details
Included in Highway Safety Manual?	No
Date Added to Clearinghouse:	
Comments:	
[View the Full Study Details]	Export PDF  Export this detail page as a PDF file

For more information, contact **Karen Scurry**, FHWA Office of Safety Programs 609-637-4207



**CMF ID: 198** 

### **Increased pavement friction**

**Description:** 

**Prior Condition: No Prior Condition(s)** 

**Category: Roadway** 

**Study:** Crash Reduction Factors for Traffic Engineering and ITS Improvements, Harkey et al., 2008

Star Quality Rating: \*\*\*\*\*\*\*\*

Crash Modification Factor (CMF)	
Value:	0.7
Adjusted Standard Error:	0.05
Unadjusted Standard Error:	

Crash Reduction Factor (CRF)	
Value:	30 (This value indicates a <b>decrease</b> in crashes)
Adjusted Standard Error:	5
Unadjusted Standard Error:	

Applicability Applicability	
Crash Type:	Single vehicle
Crash Severity:	All
Roadway Types:	All
Number of Lanes:	
Road Division Type:	
Speed Limit:	

Area Type:	All
Traffic Volume:	Minimum of All to Maximum of All
Time of Day:	
	If countermeasure is intersection-based
Intersection Type:	
Intersection Geometry:	
Traffic Control:	
Major Road Traffic Volume:	
Minor Road Traffic Volume:	
	Development Details
Date Range of Data Used:	
Municipality:	
State:	
Country:	
Type of Methodology Used:	Before/after using empirical Bayes or full Bayes
Sample Size Used:	
	Other Details
Included in Highway Safety Manual?	No
Date Added to Clearinghouse:	
Comments:	
[View the Full Study Details]	Export PDF  Export this detail page as a PDF file

For more information, contact **Karen Scurry**, FHWA Office of Safety Programs 609-637-4207



**CMF ID: 874** 

#### Narrow cross section (4 to 3 lanes with two way left-turn lane)

**Description:** 

Prior Condition: Four-lane cross-section, two in each direction.

**Category: Roadway** 

**Study:** The Safety and Operational Effects of Road Diet Conversion in Minnesota, Gates et al., 2007

Star Quality Rating: \*\*\*\*\* [View score details]

Crash Modification Factor (CMF)	
Value:	0.63
Adjusted Standard Error:	
Unadjusted Standard Error:	0.00632455532034

Crash Reduction Factor (CRF)	
Value:	37 (This value indicates a <b>decrease</b> in crashes)
Adjusted Standard Error:	
Unadjusted Standard Error:	0.632455532034

Applicability	
Crash Type:	All
Crash Severity:	All
Roadway Types:	Not specified
Number of Lanes:	4
Road Division Type:	Undivided
Speed Limit:	

Own Orealinghouse - Fown / Orkin Details
Urban
If countermeasure is intersection-based
Development Details
MN
Simple before/after
Crashes
516 Crashes
811 Crashes
Other Details

Other Details	
Included in Highway Safety Manual?	No
Date Added to Clearinghouse:	
Comments:	

[View the Full Study Details]

**Export PDF** 

Export this detail page as a PDF file

This site is funded by the U.S. Department of Transportation Federal Highway Administration and maintained by the University of North Carolina Highway Safety Research Center

For more information, contact **Karen Scurry**, FHWA Office of Safety Programs 609-637-4207



**CMF ID: 3072** 

# Change number of traffic signal cycles per hour on arterial with signal coordination from X to Y

**Description:** 

Prior Condition: No Prior Condition(s)

Category: Intersection traffic control

Study: Safety Effect of Arterial Signal Coordination, Wei and Tarko, 2011

#### **Crash Modification Factor (CMF)**

Value:  $100 * (1 - e^{-0.0444(Y-X)})$ 

**Adjusted Standard Error:** 

**Unadjusted Standard Error:** 

#### **Crash Reduction Factor (CRF)**

Value:  $e^{-0.0444(Y-X)}$ 

**Adjusted Standard Error:** 

**Unadjusted Standard Error:** 

Applicability	
Crash Type:	Rear end
Crash Severity:	All
Roadway Types:	All
Number of Lanes:	1 to 3

Road Division Type:	
Speed Limit:	30-50 mph
Area Type:	Urban and suburban
Traffic Volume:	
Time of Day:	All
If countermeasure is intersection-based	
Intersection Type:	Roadway/roadway (not interchange related)
Intersection Geometry:	
Traffic Control:	Signalized
Major Road Traffic Volume:	Maximum of 1840 veh/hr/ln Vehicles Per Hour
Minor Road Traffic Volume:	

Development Details	
Date Range of Data Used:	2003 to 2006
Municipality:	
State:	IN
Country:	USA
Type of Methodology Used:	Regression cross-section
Sample Size Used:	324 Crashes

Other Details	
Included in Highway Safety Manual?	No
Date Added to Clearinghouse:	
Comments:	

[View the Full Study Details]

**Export PDF** 

Export this detail page as a PDF file

This site is funded by the U.S. Department of Transportation Federal Highway Administration and maintained by the University of North Parolina Highway Safety Research Center

For more information, contact **Karen Scurry**, FHWA Office of Safety Programs 609-637-4207



**CMF ID: 7848** 

### Install a traffic signal

**Description:** 

**Prior Condition: Stop-Controlled Intersections** 

**Category: Intersection traffic control** 

Study: Validation and Application of Highway Safety Manual (Part D) in Florida, Abdel-Aty et al., 2014

Star Quality Rating: \*\*\*\*\* [View score details]

Crash Modification Factor (CMF)	
Value:	0.61
Adjusted Standard Error:	
Unadjusted Standard Error:	0.06

Crash Reduction Factor (CRF)	
Value:	39 (This value indicates a <b>decrease</b> in crashes)
Adjusted Standard Error:	
Unadjusted Standard Error:	6

Applicability Applicability	
Crash Type:	All
Crash Severity:	All
Roadway Types:	Not specified
Number of Lanes:	
Road Division Type:	
Speed Limit:	

Area Type:	Urban
Traffic Volume:	
Time of Day:	All
If countermeasure is intersection-based	
Intersection Type:	Not specified
Intersection Geometry:	4-leg
Traffic Control:	Stop-controlled
Major Road Traffic Volume:	
Minor Road Traffic Volume:	

Development Details	
Date Range of Data Used:	2005 to 2009
Municipality:	
State:	FL
Country:	USA
Type of Methodology Used:	Before/after using empirical Bayes or full Bayes
Sample Size Used:	

Other Details	
Included in Highway Safety Manual?	No
Date Added to Clearinghouse:	Mar-08-2016
Comments:	

[View the Full Study Details]

**Export PDF** 

Export this detail page as a PDF file

This site is funded by the U.S. Department of Transportation Federal Highway Administration and maintained by the University of North Carolina Highway Safety Research Center

For more information, contact Karen Scurry, FHWA Office of Safety Programs 609-637-4207

#### **CSAH 66 Reconstruction**

#### **Risk Assessment: Additional Comments / Explanations**

- 1. Project Scope
  - A work group of key agency, neighborhood and advocacy groups was developed as part of the Bassett Creek Trail Feasibility Study.
  - Public open house meetings have occurred as part of the trail feasibility study.
  - A general public engagement process with respect to the roadway improvements is planned with expanded business contacts.
- 2. Layout or Preliminary Plan
  - Typical sections developed
  - Concept layout underway
- 3. Environmental Documentation
- 4. Review of Section 106 Historic Resources
- 5. Review of Section 4f / 6f Resources
  - Project is adjacent to Scheid and Sochacki Parks (Golden Valley) and Theodore Wirth Parkway (Minneapolis)
  - No known adverse impacts.
- 6. Right-of-Way
  - Trail feasibility study identified areas of potential right-of-way needs and possible construction easement requirements.
- 7. Railroad Involvement
- 8. Interchange Approval
- 9. Construction Documents
- 10. Letting
  - Anticipated October 2020